

SURVEY & REMONUMENTATION

APR 28 1995

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

COMMISSION AND CORNER RECORDATION CERTIFICATE 94 DEC 16 AM 9:23

Filing Requirement of Act 74, Mich. P.A. 1970
Kent County Remonumentation

For corners in

Kent (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	J-3 (S 1/4 cor, Sec 2)
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

W. J. Bond
REG. OF DEEDS

7864

Register of Deeds Stamp & File Number

I, James C. Glaza, in a field survey on November 21, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3										▲			
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-3	1831	G.L.O.	Mullett	set post
	1849-1964	W & W notes	-----	post-stone-iron
	1973	Kent Co. Wit.	-----	iron
	1973	LCRC #381	Spicer	iron
	1985	LCRC #4234	Byl	set Kent Co. Mon.
	1991	LCRC #6387	Marschall	Kent Co. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on May 20, 1985 and was recorded per LCRC #4234.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-3 Found standard Kent Co. Mon. (Harrison) per witnesses from LCRC #4234 as set by William R. Byl in place of the iron he found and per witnesses from LCRC #6387.
LCRC #6387

Nail & tag in W side 14" Elm	S30°W	135.54'
Nail & tag in W side 6" Locust	S02°W	47.61'
Nail & tag in W side 14" Locust	S16°E	59.20'
Nail & tag in S side P.P.	N73°E	162.07'
Nail & tag in N side P.P.	N60°W	134.07'
Mon. is East of intersection of Hoag Ave. more or less 200'.		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-3 Standard Kent County Monument

Nail & K.C. remon tag in W side 14" Elm	S30°W	135.54'
Nail & K.C. remon tag in W side 6" Locust	S02°W	47.61'
Nail & K.C. remon tag in W side 18" Locust	S16°E	59.20'
Nail & K.C. remon tag in S side P.P.	N73°E	162.07'
Nail & K.C. remon tag in N side P.P.	N60°W	134.07'
Mon. is East of intersection of Hoag Ave. more or less 200'.		

P.A. 345 1990 KENT COUNTY

PEER APPROVED *10/12/94*

CHAIRMAN *James C. Glaza*

Date December 8, 1994

Signed by James C. Glaza
Surveyor's Michigan License No. Glaza & Associates, Inc. 40166

