

SURVEY & REMONUMENTATION

\$7.00
\$2.00

APR 28 1995 LAND CORNER RECORDATION CERTIFICATE

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
DEC 16 AM 9:23

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970
Kent County Remonumentation

For corners in

Kent
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|--------------------------|-------------------------|
| 1. Public Land Survey | T <u>7N</u> R <u>11W</u> | J-4 (Center,
Sec 11) |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |

W. J. Bond
REG. OF DEEDS

7865

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, James C. Glaza, in a field survey on December 2, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-4 This corner was not originally set by the G.L.O.

1940-1953	survey records	Williams & Works	stone & iron
1963	survey records	Williams & Works	set "T" iron @ intersection
1977	survey records	Williams & Works	found "T" iron of 1/4 lines
1977	LCRC #1104	Merdzinski	found "T" iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-4 Found "T" iron as set by Williams & Works in 1963. All previous witnesses from LCRC #1104 gone except for the 2" steel fence post. This "T" iron is 2.5' South and 0.4' East of the intersection of 1/4 lines. Accepted "T" iron as center of section.

LCRC #1104

"T" iron next to 2" steel fence post

Nail in N side	16" Oak	S80°E	29.0'
Nail in E side	16" Oak	N15°E	18.3'
Nail in W side	4" Oak	N85°W	11.70'
Nail in SW side	20" Maple	S30°E	39.05'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 9/22/94
CHAIRMAN *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-4 Replaced "T" iron with a standard 4" x 30" Kent County Monument.

Set Nail & K.C. remon tag in S side	5" Oak	S85°W	11.74'
Set Nail & K.C. remon tag in E side	8" Maple	S05°W	19.55'
Set Nail & K.C. remon tag in N side	5" Hickory	S85°E	2.98'
Set Nail & K.C. remon tag in N side	8" Oak	N70°E	10.10'
Set Nail & K.C. remon tag in E side	22" Oak	N05°W	26.02'

Signed by James C. Glaza
Glaza & Associates, Inc. 40166
Surveyor's Michigan License No. _____

Date December 13, 1994

