

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970
Kent County Remonumentation

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

DEC 16 AM 9:24

Tim J. Glaza
REG. OF DEEDS

7867

Register of Deeds Stamp & File Number

For corners in

Kent

(County)

Located In:

Corner Code ##

- | | | |
|------------------------------------|--------------------------|----------------------|
| 1. Public Land Survey | T <u>7N</u> R <u>11W</u> | J-6 (Center, Sec 14) |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	15		17		16		15		13				
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James C. Glaza, in a field survey on December 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-6 This corner was not originally set by the G.L.O.

1929-1946	survey records	Williams & Works	leaded stone
1965	survey records	Williams & Works	set "T" iron @ intersection of
1978	LCRC #1174	Merdzinski	"T" iron $\frac{1}{4}$ lines
1994	survey records	Glaza & Associates	Kent Co. Mon.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-6 Found standard Kent Co. Monument. Remaining witnesses check with those recorded in 1978 (LCRC #1174) by John A. Merdzinski. This monument is 0.2' South and 0.8' West of the intersection of the $\frac{1}{4}$ lines. The Kent County Remonumentation Peer Group approved the monument as the center of section.

LCRC #1174

14" Maple	N85°E	16.73'
16" Oak	S10°W	10.78'
16" Oak	S45°W	33.15'
4" Basswood	N15°W	27.05'
Corner fence post (fence E/W/S)	7.0'W & 1.5'N	

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-6 Standard Kent County Monument

K.C. remon tag & nail in S side	18" Maple	N85°E	16.73'
K.C. remon tag & nail in E side	16" Oak	S10°W	10.78'
K.C. remon tag & nail in SE side	18" Oak	S45°W	33.15'
Set K.C. remon tag & nail in E side	10" Basswood	N15°W	26.92'
Set K.C. remon tag & nail in W side	12" Elm	North	35.84'

P.A. 345 1990 KENT COUNTY

PEER APPROVED *9/22/94*
CHAIRMAN *Henry P. ...*

December 12, 1994

Signed by *James C. Glaza*
Surveyor's Michigan License No. _____, Inc. 40166

