

**SURVEY & REMONUMENTATION**

\$7.00  
\$2.00

APR 28 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970  
Kent County Remonumentation

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

94 DEC 16 AM 9:24

For corners in

Kent (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	J-7 (S 1/2 cor, Sec 14)
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Lucy Bond*  
REG. OF DEEDS

7868

Register of Deeds Stamp & File Number

I, James C. Glaza, in a field survey on December 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-7	1831	G.L.O.	Mullett	set post
	1972	Kent Co. Wit.	-----	iron
	1972	LCRC #170	Bonnema	iron
	1982	LCRC #2778	Merdzinski	set Kent Co. Mon.
	1988	LCRC #5097	Brintnall	Kent Co. Mon.
	1991	LCRC #6389	Marschall	Kent Co. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on March 8, 1982 and was recorded per LCRC #2778.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-7 Found broken Kent Co. Mon. (Harrison) per witnesses from LCRC # 2778 as set by John A. Merdzinski in place of the iron he found and per witnesses from LCRC #5097 and LCRC #6389.

LCRC #6389

Nail & tag in S side P.P.	N74°W	111.59'
Nail & tag in S side T.P.	S75°E	109.92'
C/L top nut hyd.	N78°E	136.09'
R.L.S. iron	South	32.65'
SE corner brick garage	N29°E	139.55'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-7 Replace broken mon. with standard (4"x30") Kent Co. Mon. (Harrison) in mon. box.

Nail & K.C. remon tag in S side P.P.	N74°W	111.59'
Nail & K.C. remon tag in S side T.P.	S75°E	109.92'
C/L top nut hyd.	N78°E	136.09'
R.L.S. iron	South	32.57'
SE corner brick garage	N29°E	139.55'

C/L East-West bit. road 1' North

P.A. 345 1990 KENT COUNTY

PEER APPROVED *10/12/94*

CHAIRMAN *[Signature]*

Date December 8, 1994



Signed by *James C. Glaza*  
Glaza & Associates, Inc. 40166  
Surveyor's Michigan License No. \_\_\_\_\_