

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94 DEC 29 AM 11:13

For corners in

<u>Kent</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	<u>J-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Eric J. Bond
REG. OF DEEDS

7962

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on July 20 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-10 This corner was not originally set by the G.L.O.

1935	Survey Records	Williams & Works	Set Iron
1935-1960	Survey Records	Williams & Works	Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-10 In 1935 Williams & Works established the Center Section at the intersection of 1/4 lines and had used this location for all future surveys. In 1960's this corner was destroyed by the construction of I-96 (no corner shown on MDOT right-of-way drawings). Re-establish corner at the intersection of 1/4 lines. Checks dist. shown in Williams & Works 1935 and 1956 survey records to E 1/4, W 1/4 within 2' ± and to N 1/4 within 0.1 ±.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 4/17/94
CHAIRMAN *Henry Huber*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-10 Set Standard 4" x 30" Kent County Monument.

- Nail & K.C. remon. tag in N side 6" Box Elder S 80° E 122.91'
- Nail & K.C. remon. tag in N side 14" Box Elder S 85° W 143.40'
- SE cor. of South end West Abutment of M-21 overpass N 85° W 182.82'
- SE cor. of South column West side Westbound M-21 overpass N 75° W 129.20'
- SE cor. of South column East side overpass N 50° W 62.42'



Signed by *Randy J. Kolehouse* Date 12/12/94
Surveyor's Michigan License No. 25854

