

SURVEY & REMONUMENTATION

\$7.00
\$2.00

APR 28 1995

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
94 DEC 16 AM 9:24

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Kent County Remonumentation

For corners in **COMMISSION**
Kent
(County)

Located In: Corner Code #

| | | |
|------------------------------------|--------------------------|---|
| 1. Public Land Survey | T <u>7N</u> R <u>11W</u> | K-1 (NE cor, Sec 2) (common corner) |
| | T _____ R _____ | |
| | T _____ R _____ | |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |

REG. OF DEEDS

7869

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, James C. Glaza, in a field survey on November 21, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| | | | | |
|-----|---------|---------------|------------|-------------------|
| K-1 | 1831 | G.L.O. | Lyon | set post |
| | No Date | Kent Co. Wit. | ----- | leaded stone |
| | 1973 | LCRC #555 | Vankooten | leaded stone |
| | 1974 | LCRC #692 | Bonnema | square spike |
| | 1981 | LCRC #1787 | Merdzinski | set Kent Co. Mon. |
| | 1988 | LCRC #4875 | Bueche | Kent Co. Mon. |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on January 22, 1981 and was recorded per LCRC #1787.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1 Found standard Kent Co. Mon. (Harrison) per witnesses from LCRC #1787 as set by John A. Merdzinski in place of an iron he found and per witnesses from LCRC #4875.
LCRC #4875

| | | |
|---|-------|--------|
| SW corner frame garage | N20°E | 86.75' |
| K.C. remon tag & nail in SE side 22" Oak | N30°E | 28.87' |
| K.C. remon tag & nail in NW side 16" Twin Oak | S35°W | 28.08' |
| K.C. remon tag & nail in E side T. pole | S05°W | 52.64' |
| K.C. remon tag & nail in W side 12" Pine | S45°E | 39.58' |
| K.C. remon tag & nail in N side 10" Pine | S64°E | 80.21' |
| Stone | N05°E | 33.46' |

On C/L bit. E & W, old fence S

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1 Standard Kent County Monument

| | | |
|---|-------|--------|
| SW corner frame garage | N20°E | 86.75' |
| K.C. remon tag & nail in SE side 24" Oak | N30°E | 28.87' |
| K.C. remon tag & nail in NW side 20" Twin Oak | S35°W | 28.04' |
| K.C. remon tag & nail in W side 8" Pine | S45°E | 39.62' |
| K.C. remon tag & nail in N side 8" Pine | S64°E | 80.21' |

On C/L bit. E & W, old fence S

P.A. 345 1990 KENT COUNTY

PEER APPROVED 10/12/94

CHAIRMAN [Signature]

Signed by [Signature]
Glaza & Associates, Inc.

Date December 9, 1994

Surveyor's Michigan License No. 40166

