

SURVEY &

\$7.00 REMONUMENTATION

\$2.00

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970
Kent County Remonumentation

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94 DEC 16 AM 9:24

For corners in **COMMISSION**

Kent
(County)

Located In:

Corner Code #

1. Public Land Survey	T	7N	R	11W	K-2 (E 1/4 cor, Sec 2)
	T		R		
	T		R		
	T		R		
2. Property Controlling In Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

W. J. Bond
REG. OF DEEDS

7870

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, James C. Glaza, in a field survey on November 2, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-2	1831	G.L.O.	Mullett	set post
	No Date	Kent Co. Wit.	-----	stake
	1982	LCRC #3557	VanKooten	axle shaft
	1985	LCRC #4247	Byl	set Kent Co. Mon.
	1991	LCRC #6392	Marschall	Kent Co. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on January 10, 1985 and was recorded per LCRC #4247.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-2 Found standard Kent Co. Mon. (Harrison) per witnesses from LCRC #4247 as set by William R. Byl in place of the axle shaft he found and per witnesses from LCRC #6392.

LCRC #6392

Nail & tag in W side	24" Oak	S30°E	4.35'
Nail & tag in E side	27" Oak	N00°E	21.59'
Nail & tag in E side	24" Oak	N30°W	12.62'
Nail & tag in N side	15" Oak	N90°E	11.89'
Nail & tag in S side	27" Oak	S90°W	29.99'
Nail & tag in W side	27" Oak (6' above ground)	S00°W	48.94'
E-W fence line	S more or less 1'		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2 Standard Kent County Monument

Nail & K.C. remon tag in W side	24" Oak	S30°E	4.35'
Nail & K.C. remon tag in E side	27" Oak	N00°E	21.59'
Nail & K.C. remon tag in E side	24" Oak	N30°W	12.62'
Nail & K.C. remon tag in N side	15" Oak	N90°E	11.89'
Nail & K.C. remon tag in S side	27" Oak	S90°W	30.00'
Nail & K.C. remon tag in w side	27" Oak (6' abv grd)	S00°W	48.96'
E-W fence line	S more or less 1'		
In remnants of N-S fence line			

P.A. 345 1990 KENT COUNTY
PEER APPROVED 10/12/99
CHAIRMAN Harry Huber

Date December 8, 1994



Signed by James C. Glaza
Glaza & Associates, Inc.

Surveyor's Michigan License No. 40166