

SURVEY & REMONUMENTATION

\$7.00
\$2.00

APR 28 1995

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

DEC 16 AM 9:24

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Kent County Remonumentation

For corners in

Kent (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	K-4 (E 1/4 cor, Sec 11)
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Tracy J. Glaza
REG. OF DEEDS

7872

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James C. Glaza, in a field survey on November 21, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-4	1831	G.L.O.	Mullett	set post
	1956	Kent Co. Wit.	-----	stone & iron
	1975	LCRC #867	Nederveld	"T" iron
	1982	LCRC #2781	Merdzinski	set Kent Co. Mon.
	1991	LCRC #6394	Marschall	Kent Co. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on March 4, 1982 and was recorded per LCRC #2781.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-4 Found standard Kent Co. Mon. (Harrison) per witnesses from LCRC #2781 as set by John A. Merdzinski in place of a "T" iron he found and per witnesses from LCRC #6394.
LCRC #6394

Nail & tag in S side 16" Walnut	East	12.75'
Nail & tag in W side 12" Oak	S15°E	13.79'
Nail & tag in E side 10" Ash	S30°W	11.86'
Nail & tag in E side 16" Tri. Walnut	S01°E	30.71'
Nail & tag in W side 14" Ash	N15°E	13.82'
Nail & tag in SW side 12" Oak	N55°E	1.16'

C/L blacktop road (Maguire Ave.) is more or less 41' West of corner.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4 Standard Kent County Monument

Nail & K.C. remon tag in S side 18" Walnut	East	12.75'
Set Nail & K.C. remon tag in W side 12" Oak	S15°E	13.77'
Set Nail & K.C. remon tag in E side 10" Ash	S30°W	11.86'
Set Nail & K.C. remon tag in E side 18" Tri. Walnut	S01°E	30.70'
Set Nail & K.C. remon tag in W side 16" Ash	N15°E	13.82'
Set Nail & K.C. remon tag in NW side 12" Oak	N55°E	1.75'

C/L blacktop road (Maguire Ave.) is more or less 41' West of corner.

P.A. 343 10" Kent County

PEER APPROVED 10/12/94
CHAIRMAN Henry J. [Signature] Date December 8, 1994

Signed by James C. Glaza
Surveyor's Michigan License No. 40166
Glaza & Associates, Inc.

