

**SURVEY & REMONUMENTATION**  
**\$7.00**  
**\$2.00**

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**Kent County Remonumentation**

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD

94 DEC 16 AM 9:24

For corners in

**Kent** **COMMISSION**  
 (County)

Located In:

Corner Code #

1. Public Land Survey	T	7N	R	11W	K-5 (NE cor, Sec 14)
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

*Tim J. Glaza*  
 REG. OF DEEDS

7873

Register of Deeds Stamp & File Number

- 4 Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5 Private Claims \_\_\_\_\_

I, James C. Glaza, in a field survey on November 21, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

K-5	1831	G.L.O.	Mullett	set post
	1961	Kent Co. Wit.	-----	iron
	1975	LCRC #867	Nederveld	iron
	1982	LCRC #2782	Merdzinski	set Kent Co. Mon.
	1991	LCRC #6395	Marschall	Kent Co. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on March 5, 1982 and was recorded per LCRC #2782.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

K-5 Found standard Kent Co. Mon. (Harrison) per witnesses from LCRC #2782 as set by John A. Merdzinski in place of the 1/2" iron pipe he found and per witnesses from LCRC #6395.

LCRC #6395

Nail & tag in N side	26" Maple	S70°W	51.02'
Nail & tag in W side	14" W. Cherry	S15°W	24.95'
Leaded stone		S00°E	33.05'
Nail & tag in SE side	6" Ash	N42°E	42.01'
Nail & tag in N side	14" Maple	S75°E	74.21'
C/L pavement N more or less	12.00'		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-5 Standard Kent County Monument

Nail & K.C. remon tag in N side	26" Maple	S70°W	51.02'
Nail & K.C. remon tag in W side	14" W. Cherry	S15°W	24.95'
Nail & K.C. remon tag in SE side	10" Ash	N42°E	42.04'
Nail & K.C. remon tag in N side	14" Maple	S75°E	74.30'
C/L pavement N more or less	12.00'		

P.A. 345 1990 KENT COUNTY

PEER APPROVED 10/12/94

CHAIRMAN *Harry Fisher*



Signed by *James C. Glaza*  
 Glaza & Associates, Inc.

Date December 8, 1994

Surveyor's Michigan License No. 40166