

**SURVEY & REMONUMENTATION**

\$7.00  
\$2.00

APR 28 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970  
Kent County Remonumentation

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

94 DEC 16 AM 9:24

For corners in

Kent (County)	Located In:	Corner Code #
1. Public Land Survey	T 7N R 11W	K-6 (E 1/4 cor, Sec 14)
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*W. J. Bond*  
REG. OF DEEDS

7874

Register of Deeds Stamp & File Number

I, James C. Glaza, in a field survey on December 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented; re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

K-6	1831	G.L.O.	Mullett	set post
	1895-1970	W & W notes	-----	leaded stone
	1956	Kent Co. Wit.	-----	stone and iron
	1985	LCRC #4248	Byl	set Kent Co. Mon.
	1991	LCRC #6396	Marschall	Kent Co. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William Byl on January 10, 1985 and was recorded per LCRC #4248.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

K-6. Found standard Kent Co. Mon. (Harrison) per witnesses from LCRC #4248 as set by William Byl in place of a leaded stone he found and per witnesses from LCRC #6396.  
LCRC #6396

K.C. remon tag & nail in N side 12"-24" Twin Basswood	N50°W	23.77'	(6' abv. grd.)
K.C. remon tag & nail in E side 14" Oak (6' above ground)	N00°E	28.44'	
K.C. remon tag & nail in E side 18" Ash	N45°E	31.37'	
K.C. remon tag & nail in E side 26" Beech	S40°W	21.04'	
K.C. remon tag & nail in N side 18" Oak	N85°E	39.00'	
Remains of fence to N-S & E-W.			

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-6 Standard Kent County Monument

K.C. remon tag & nail in N side 12"-24" Twin Basswood	N50°W	23.77'	(6' abv. grd.)
K.C. remon tag & nail in E side 14" Oak (6' above ground)	N00°E	28.44'	
K.C. remon tag & nail in E side 20" Ash	N45°E	31.37'	
K.C. remon tag & nail in E side 26" Beech	S40°W	21.04'	
K.C. remon tag & nail in N side 18" Oak	N85°E	39.00'	
Remains of fence to N-S & E-W.			

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 10/12/94  
CHAIRMAN Henry Huber

Signed by James C. Glaza  
Glaza & Associates, Inc.  
Surveyor's Michigan License No. 40166

Date December 6, 1994

