

**SURVEY & REMONUMENTATION**

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970  
 KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 94 DEC -6 AM 9:05

For corners in

**COMMISSION**

Kent (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	<u>K-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*W. J. Bond*  
 REG. OF DEEDS

7828

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on June 20 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-8	1831	G.L.O. Notes	Mullett	Set Post
	1939	Wit. Map	K.C. Surveyor	1" Iron
	1975	L.C.R.C. #868	Nederveld	"T" Iron
	1982	L.C.R.C. #2784	Williams & Works	Fnd. "T" Iron/Set K.C. Mon.

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 11/3/94  
 CHAIRMAN *Hubert Howe*

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 3/8/82 and was recorded per L.C.R.C. #2784.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8 Found standard Kent County Monument 3' M/L North of the C/L of Bradford Street running E-W per L.C.R.C.'s #2784 and #6398 as set by Williams & Works in place of a "T" iron over a 1" x 3" long iron over the remains of a 1/2" x 2" wood stake they found which checked K.C. Surveyor records and L.C.R.C. #868.

L.C.R.C. #2784

L.C.R.C. #6398


Nail & K.C. remon. tag in 16" Oak S 60° W 103.95'  
 C/L of hydrant S 70° E 93.85'  
 C/L of E & W pavement S 3.00'

Top C/L nut fire hyd. S 70° E 93.88'  
 Nail & tag SW side 14" Elm S 30° E 52.00'  
 Nail & tag E side 6" Oak S 21° W 34.91'  
 Nail & tag SE side 18" Oak S 53° W 103.91'  
 Nail & tag W side Twin 16" Maple (4' above grd.) N 28° E 29.13'  
 C/L of E-W pavement S 3' more or less

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 Standard Kent County Monument  
 Top C/L nut fire hyd. S 70° E 93.88'  
 Nail & K.C. remon. tag SW side 14" Elm S 30° E 52.00'  
 Nail & K.C. remon. tag E side 6" Oak S 21° W 34.91'  
 Nail & K.C. remon. tag SE side 18" Oak S 53° W 103.91'  
 Nail & K.C. remon. tag W side Twin 16" Maple (4' above grd.) N 28° E 29.13'  
 C/L of E-W pavement S 3' more or less



Signed by Randy Kolehouse Date 12/1/94  
 Surveyor's Michigan License No. 25854