

**SURVEY & REMONUMENTATION**

APR 28 1995

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

DEC -6 AM 9:05

For corners in

Kent (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	<u>K-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Lucy J. Bond*  
REG. OF DEEDS

7832

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Randy Kolehouse, in a field survey on July 21 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-12 1831	G.L.O. Notes	Mullett	Set Post	P.A. 345 1990 KENT COUNTY
1976	L.C.R.C. #963	Exxel Engineering	Sq. Spike & Tag	PEER APPROVED 11/17/94
1978	L.C.R.C. #1184	Williams & Works	Conc. Spike & Tag	CHAIRMAN <i>Harry Huber</i>

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 11/17/94  
CHAIRMAN *Harry Huber*

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 11/1/82 and was recorded per L.C.R.C. #3109.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-12 Found standard Kent County Monument at approximate intersection of East Paris Avenue running N-S and Cascade Road running NW & SE per L.C.R.C.'s #3109 and #6402 as set by Williams & Works in place of a concrete nail over a "+" in brick pavement 4' below concrete spike over an old bent iron they found which checked K.C. Surveyor's records and L.C.R.C.'s #963 and #1184.

L.C.R.C. #3109

L.C.R.C. #6402

Nail & K.C. remon. tag in E side p. pole N 10° W 94.88'  
Nail & K.C. remon. tag in SE side signal pole N 55° E 50.12'  
Back concrete curb N 30° E 41.75'

Nail & tag E side p. pole N 10° W 94.89'  
C/L top nut hydrant S 85° W 58.00'  
Nail & tag W side utl. pole S 63° W 34.59'  
Nail & tag E side signal pole N 57° E 50.12'  
Nail & tag E side utl. pole S 21° E 104.14'  
C/L top nut hydrant S 84° E 116.40'  
On C/L Cascade Rd. and East Paris back of curb

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12 Standard Kent County Monument  
Nail & K.C. remon. tag E side p. pole N 10° W 94.89'  
C/L top nut hydrant S 85° W 58.00'  
Nail & K.C. remon. tag W side utl. pole S 63° W 34.59'  
Nail & K.C. remon. tag E side signal pole N 57° E 50.12'  
Nail & K.C. remon. tag E side utl. pole S 21° E 104.14'  
C/L top nut hydrant S 84° E 116.40'



Signed by *Randy J. Kolehouse* Date 12/1/94  
Surveyor's Michigan License No. 25854