

SURVEY & REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD

94 DEC -6 AM 9:05

For corners in **COMMISSION**

Kent (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	<u>K-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Tracy J. Gandy
 REG. OF DEEDS

7833

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Randy Kolehouse, in a field survey on July 20 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-13	1831	G.L.O. Notes	L. Lyon	Set Post
	N/A	Wit. Map	K.C. Surveyor	Wagon Axle
	1959	Survey Records	MDSH	Wagon Axle
	1972	L.C.R.C. #360	Exxel Engineering	1/2" Iron
	1982	L.C.R.C. #3163	Williams & Works	Fnd. 1/2" Iron/Set K.C. Mon.
	1991	L.C.R.C. #6376	Marschall	K.C. Monument

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 11/3/94
 CHAIRMAN *Harry Huber*

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 11/29/82 and was recorded per L.C.R.C. #3163.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 Found standard Kent County Monument 3' M/L West oc C/L of East Paris Avenue per L.C.R.C.'s #3163 and #6376 as set by Williams & Works in place of a 1/2" iron they found which checked L.C.R.C. #360. This corner is common with K-A T6N R11W.

L.C.R.C. #3163

L.C.R.C. #6376


Nail & K.C. remon. tag in NW side p. pole N 45° E 57.64'
 Nail & K.C. remon. tag in SW side p. pole N 52° W 56.82'

Nail & tag N side 48" Oak N 80° W 63.88'
 Nail & tag N side 8" Crabapple S 55° W 57.18'
 Nail & tag SW side utl. pole N 52° W 56.65'
 Nail & Tag NW side utl. pole N 36° E 57.62'
 Nail & tag S side utl. pole N 88° E 34.25'
 Mon. is more or less 2' West of C/L East Paris

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 Standard Kent County Monument
 Nail & K.C. remon. tag N side 48" Oak N 80° W 63.88'
 Nail & K.C. remon. tag N side 8" Crabapple S 55° W 57.18'
 Nail & K.C. remon. tag SW side utl. pole N 52° W 56.65'
 Nail & K.C. remon. tag NW side utl. pole N 36° E 57.62'
 Nail & K.C. remon. tag S side utl. pole N 88° E 34.25'
 Mon. is more or less 2' West of C/L East Paris



Signed by *Randy J. Kolehouse*
 Surveyor's Michigan License No. 25854

Date 12/1/94