

SURVEY & REMONUMENTATION
\$7.00
\$2.00
APR 28 1995

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD

DEC 16 AM 9:24

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
 Kent County Remonumentation

For corners in **COMMISSION**

Kent (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	L-2 (Center, Sec 1)
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

W. J. Bond
 REG. OF DEEDS

7877

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James C. Glaza, in a field survey on November 28, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-2 This corner was not originally set by the G.L.O.

1950	survey records	Williams & Works	set axle shaft
1953	survey records	Williams & Works	axle shaft
1954	survey records	Williams & Works	axle shaft
1969	survey records	Williams & Works	axle shaft
1976	LCRC #938	Merdzinski	axle shaft
1978	LCRC #1194	Shangraw	set iron @ intersection of
1982	LCRC #2884	Hackbardt	wheel hub $\frac{1}{4}$ lines (axle shaft)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-2 Found axle shaft set by Williams & Works in 1950. This axle shaft is 2.5' South and 4.5' East of the intersection of $\frac{1}{4}$ lines. Also found iron set by Shangraw (LCRC #1194) in 1978, 3.7' NW of the axle shaft. The Kent County Remonumentation Peer Group approved the axle shaft as the center of section.

LCRC #2884

- 30" Oak W 2.05'
- 24" Db1 Oak E 50'
- 12" W. Cherry N 37.48'
- 10" Oak N30°E 44.15'

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 10/12/94
 CHAIRMAN *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-2 Replace axle with 4" x 25" Kent County Monument.

Set Nail & K.C. remon tag in NE side	34" Oak	N50°W	2.69'
Set Nail & K.C. remon tag in SE side	12" Oak	N40°E	44.39'
Set Nail & K.C. remon tag in SE side	10" Birch	S50°W	34.08'
Set Nail & K.C. remon tag in SW side	5" Oak	S60°E	26.70'

Signed by *James C. Glaza*
 Glaza & Associates, Inc.
 Surveyor's Michigan License No. 40166

Date December 13, 1994

