

**SURVEY & REMONUMENTATION**

\$7.00  
\$2.00

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970  
Kent County Remonumentation

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

94 DEC 16 AM 9:24

For corners in **COMMISSION**  
Kent  
(County)

Located In: Corner Code #

- |                                       |                          |                            |
|---------------------------------------|--------------------------|----------------------------|
| 1. Public Land Survey                 | T <u>7N</u> R <u>11W</u> | L-3 (N 1/4 cor,<br>Sec 12) |
|                                       | T _____ R _____          | _____                      |
|                                       | T _____ R _____          | _____                      |
|                                       | T _____ R _____          | _____                      |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____  | _____                      |
|                                       | S _____ T _____ R _____  | _____                      |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____  | _____                      |
|                                       | S _____ T _____ R _____  | _____                      |
| 4. Lot No. _____                      | Recorded Plat _____      |                            |
| 5. Private Claims _____               |                          |                            |

*W. J. Glaza*  
REG. OF DEEDS

7878

Register of Deeds Stamp & File Number

I, James C. Glaza, in a field survey on December 5, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

**A. Description of original monument and accessories and/or subsequent restoration:**

L-3	1831	G.L.O.	Mullett	set post
	1941	Kent Co. Wit.	-----	concrete monument
	1979	LCRC #1244	Merdzinski	concrete monument
	1982	LCRC #2785	Merdzinski	set Kent Co. Monument
	1991	LCRC #6403	Marschall	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on March 9, 1982 and was recorded per LCRC #2785.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

L-3 Found standard Kent Co. Mon. (Harrison) per witnesses from LCRC #2785 as set by John A. Merdzinski in place of the concrete monument he found, and per witnesses from LCRC #6403.

LCRC #6403

K.C. remon tag & nail in S side	18" Oak	N50°W	12.54'
K.C. remon tag & nail in E side	12" Sassafras	South	44.30'
K.C. remon tag & nail in E side	12" Twin Maple	S20°W	47.03'
K.C. remon tag & nail in S side	18" Oak	S75°E	21.36'
K.C. remon tag & nail in S side	20" Oak	N45°W	20.11'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-3 Standard Kent County Monument

K.C. remon tag & nail in S side	18" Oak	N50°W	12.54'
K.C. remon tag & nail in E side	12" Sassafras	South	44.30'
K.C. remon tag & nail in E side	12" Twin Maple	S20°W	47.03'
K.C. remon tag & nail in S side	18" Oak	S75°E	21.36'
K.C. remon tag & nail in S side	22" Oak	N45°W	20.11'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 10/12/94  
CHAIRMAN *[Signature]*

Date December 5, 1994

Signed by *[Signature]*  
Glaza & Associates, Inc.

Surveyor's Michigan License No. 40166

