

\$7.00
\$2.00

SURVEY & REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970
Kent County Remonumentation

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94 DEC 16 AM 9:24

W. J. Bond
REG. OF DEEDS

For corners in
Kent **COMMISSION**
(County)

Located In:

Corner Code #:

1. Public Land Survey	T <u>7N</u> R <u>11W</u>	L-4 (Center, Sec 12)
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

7879

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11								
6													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James C. Glaza, in a field survey on December 2, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-4 This corner was not originally set by the G.L.O.			
1909	survey records	Williams & Works	stake
1939	survey records	Williams & Works	fence corner
1941	Kent Co. Wit.	-----	concrete mon.
1975	survey records	Williams & Works	concrete mon.
1975	LCRC #867	Nederveld	concrete mon.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-4 Found concrete monument as recorded in LCRC #867 by Gordon Nederveld in 1975. This monument is 3.8' South and 0.1' East of the intersection of $\frac{1}{4}$ lines. The Kent County Remonumentation Peer Group approved the concrete monument as the center of section.

LCRC #867

Nail in 14" Oak	West	28.89'
Nail in 12" Oak	N-NW	6.20'
Nail in 10" Oak	S-SE	25.75'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-4 Replaced concrete monument with a standard 4" x 30" Kent County Monument.

Set Nail & K.C. remon tag in SW side 12" Oak	N10°W	6.20'
Set Nail & K.C. remon tag in S side 10" Oak	N80°W	17.29'
Set Nail & K.C. remon tag in NE side 10" Oak	S65°E	18.77'
Set Nail & K.C. remon tag in W side 12" Oak	S12°E	25.81'

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/22/99
CHAIRMAN Harry Stuber

Signed by James C. Glaza
Glaza & Associates, Inc. 40166
Surveyor's Michigan License No. _____

Date December 12, 1994

