

\$7.00
\$2.00

SURVEY & REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970
Kent County Remonumentation

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

DEC 16 AM 9:24

For corners in
Kent
(County)

COMMISSION

Located In:

Corner Code #

1. Public Land Survey	T	7N	R	11W	L-5 (N 1/2 cor, Sec 13)
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

James C. Glaza
REG. OF DEEDS

7880

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

I, James C. Glaza, in a field survey on November 28, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-5	1831	G.L.O.	Mullett	set post
	1972	Kent Co. Wit.	-----	iron pipe
	1972	LCRC #281	VanKooten	iron pipe
	1982	LCRC #2786	Merdzinski	set Kent Co. Mon.
	1991	LCRC #6404	Marschall	Kent Co. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on March 5, 1982 and was recorded per LCRC #2786.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-5 Found standard Kent Co. Mon. (Harrison) per witnesses from LCRC #2786 as set by John A. Merdzinski in place of the iron pipe he found and per witnesses from LCRC #6404.

LCRC #6404

Nail & tag in W side utility pole	S13°E	51.20'
Nail & tag in S side 26" Oak	N84°W	66.28'
Nail & tag in E side 36" Oak	N38°W	26.50'
Nail & tag in S side 40" Oak	N76°E	49.40'
SE corner concrete porch platform	N45°E	91.63'
SW corner house foundation	N30°E	85.42'

The selected location is accepted by me and is generally accepted by professional surveyors at the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5 Standard Kent County Monument

Nail & K.C. remon tag in W side utility pole	S13°E	51.27'
Nail & K.C. remon tag in S side 26" Oak	N84°W	66.28'
Nail & K.C. remon tag in E side 36" Oak	N38°W	26.51'
Nail & K.C. remon tag in S side 40" Oak	N76°E	49.42'
SE corner concrete porch platform	N45°E	91.62'
SW corner house foundation	N30°E	85.44'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 10/12/99

CHAIRMAN Henry Huber

Date December 7, 1994

Signed by

James C. Glaza
Glaza & Associates, Inc.

Surveyor's Michigan License No.

40166

