

Y.V.

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

93 MAR 23 AM 8:24

W. J. Bond
REG. OF DEEDS

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Kent

(County)

Located In:

Grand Rapids Twp.
Corner Code #/

- 1. Public Land Survey T 7N R 11W
- T _____ R _____
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

L-6
Sec. 13
Center

Sequence #1

6738

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, **Thomas W. Chettleburgh**, in a field survey on **February 24**, 19**93** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

MVK - 1972 L.C.R.C. 281
 Found 1" Iron at corner
 Spike in 14" Oak S 20.10'
 Spike in 12" Oak SSE 10.90'
 Spike in 10" Oak NE 19.93'
 Spike in 20" Oak NW 18.53'

Exxel - Found iron 0.96' W of N-S 1/4 line.
 Held iron for corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found above iron from witnesses.
 Intersection of 1/4 lines 0.70'S & 0.84'E.
 Set Kent County Harrison Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Kent County Harrison Monument

| | | |
|---------------------------|-------|--------|
| Nail/Tag N. side 6" Maple | N77°E | 35.55' |
| Nail/Tag N. side 6" Oak | S89°E | 28.40' |
| Nail/Tag N. side 6" Maple | S65°W | 37.93' |
| Nail/Tag S. side 21" Oak | S80°W | 41.02' |
| Nail/Tag SE side 12" Oak | N50°E | 20.00' |
| Nail/Tag W. side 16" Oak | S20°E | 14.95' |
| Nail/Tag W. side 18" Oak | S05°W | 20.19' |
| Nail/Tag NE side 16" Oak | N30°W | 18.33' |



Signed by *Thomas W. Chettleburgh*

Date **March 11, 1993**

Surveyor's Michigan License No. **16036**