

**SURVEY & REMONUMENTATION**

\$7.00  
\$2.00

APR 28 1995

*NU*  
*Seg 2*

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

DEC 16 AM 9:24

**LAND CORNER RECORDATION CERTIFICATE**  
**COMMISSION**

Filing Requirement of Act 74, Mich. P.A. 1970  
Kent County Remonumentation

For corners in

Kent (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	L-6 (Center, Sec 13)
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*W. J. Bond*  
REG. OF DEEDS

7881

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James C. Glaza, in a field survey on December 2, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

L-6 This corner not originally set by the G.L.O.			
1952	W & W notes	-----	set iron intersection of 1/4 lines
1967	W & W notes	-----	found iron
1972	Kent Co. Wit.	-----	found iron
1972	LCRC #281	VanKooten	found iron
1993	LCRC #6738	Chettleburgh	set Kent Co. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Thomas W. Chettleburgh on February 24, 1993 and was recorded per LCRC #6738.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

L-6 Found standard Kent Co. Mon. (Harrison) per witnesses from LCRC #6738 as set by Thomas W. Chettleburgh in place of a iron he found.

LCRC #6738			
Nail & tag in N side	6" Maple	N77°E	35.55'
Nail & tag in N side	6" Oak	S89°E	28.40'
Nail & tag in N side	6" Maple	S65°W	37.93'
Nail & tag in S side	21" Oak	S80°W	41.02'
Nail & tag in SE side	12" Oak	N50°E	20.00'
Nail & tag in W side	16" Oak	S20°E	14.95'
Nail & tag in W side	18" Oak	S05°W	20.19'
Nail & tag in NE side	16" Oak	N30°W	18.33'

Intersection of 1/4 lines 0.70'S and 0.84'E  
The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-6 Found Standard Kent County Monument			
Nail & K.C. remon tag in N side	6" Maple	N77°E	35.55'
Nail & K.C. remon tag in N side	6" Oak	S89°E	28.40'
Nail & K.C. remon tag in N side	6" Maple	S65°W	37.86'
Nail & K.C. remon tag in S side	21" Oak	S80°W	41.02'
Nail & K.C. remon tag in SE side	12" Oak	N50°E	19.90'
Nail & K.C. remon tag in W side	16" Oak	S20°E	14.95'
Nail & K.C. remon tag in W side	18" Oak	S05°W	20.19'
Nail & K.C. remon tag in NE side	16" Oak	N30°W	18.28'

Intersection of 1/4 lines 0.6' S and 0.8' E

Signed by James C. Glaza Date December 8, 1994  
Surveyor's Michigan License No. 40166

PEER APPROVED  
CHAIRMAN  
1990 KENT COUNTY  
2/12/94  
*Thomas W. Chettleburgh*

