

SURVEY & REMONUMENTATION

\$7.00
\$2.00

APR 28 1995

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
94
DEC 16 AM 9:24

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970
Kent County Remonumentation

For corners in

Kent (County)	Located In:	Corner Code -#
1. Public Land Survey	T 7N R 11W	L-7 (S 1/4 cor, Sec 13)
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Wendell Bond
REG. OF DEEDS

7882

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James C. Glaza, in a field survey on November 25, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-7 1831	G.L.O.	Mullett	set post
1964	Kent Co. Wit.	-----	iron pipe
1978	LCRC #1129	Merdzinski	iron pipe
1982	LCRC #2787	Merdzinski	set Kent Co. Mon.
1987	W & W	-----	Kent Co. Mon.
1990	LCRC #5709	Bueche	set Kent Co. Mon.
1991	LCRC #6405	Marschall	Kent Co. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on March 5, 1982 and was recorded per LCRC #2787.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-7 Found Kent Co. Mon. (Harrison) per witnesses from LCRC #5709 as set by John C. Bueche and per witnesses from LCRC #6405. The county mon. set per LCRC #2787 was destroyed due to road construction.

LCRC #6405

Iron	S45°E	100.01'
Nail & tag in North side 10" Cedar	S70°W	124.12'
Nail & tag in S'ly side 1' dia. fence post	N65°E	100.52'
Nail & tag in West side 14" Apple	N25°E	91.27'

On C/L blacktop E-W & South.

The selected location is accepted by me and is generally accepted by professional surveyor's as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7 Standard Kent County Monument

Iron	S45°E	100.01'
Nail & tag in S'ly side 1' dia. fence post	N65°E	100.52'
Nail & tag in West side 16" Apple	N25°E	91.27'
Set Nail & tag in North side Triple Cedar	S55°W	98.65'

P.A. 345 1990 KENT COUNTY
PEER APPROVED 10/12/94
CHAIRMAN *Harry Shubert*
Date December 7, 1994



Signed by *James C. Glaza*
Surveyor's Michigan License No. 40166
Glaza & Associates, Inc.