

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970-6 AM 9:05
KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

For corners in

Kent (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	<u>L-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

W. J. K.
REG. OF DEEDS

7834
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randy Kolehouse, in a field survey on June 10 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-9	1831	G.L.O. Notes	Mullett	Set Post	P.A. 345 1990 KENT COUNTY
	1944	Wit. Map	K.C. Surveyor	1" Iron	PEER APPROVED <u>10/12/94</u>
	1978	L.C.R.C. #1129	Williams & Works	1" Pipe	CHAIRMAN <u>Henry Ober</u>
	1982	L.C.R.C. #3276	C. Hay	Fnd. Iron/Set K.C. Mon.	
	1990	L.C.R.C. #5711-A	Bueche	Reset K.C. Mon.	
	1991	L.C.R.C. #6406	Marschall	K.C. Monument	

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Clayton Hay on 3/10/82 and was recorded per L.C.R.C. #3276.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9 Found standard Kent County Monument at the C/L intersection of Michigan Street running E-W and Crahn Avenue running N-S per L.C.R.C.'s #5711-A and #6406 as reset by John Bueche at location of K.C. monument set by C. Hay in place of a 1" pipe over a 1/2" pipe over a 3/4" iron which checked L.C.R.C. #1129.

L.C.R.C. #5711-A

L.C.R.C. #6406


SE cor. metal base to MBT box N 80° W 176.20'
Remon. tag & nail in N'ly side p. pole S 35° E 91.48'
Remon. tag & nail in N'ly side p. pole N 70° E 79.45'
On C/L blacktop E-W and N-S

Nail & tag N side p. pole S 35° E 91.39'
Nail & tag N side p. pole N 70° E 79.47'
Nail & tag N side 4" Poplar S 72° W 112.53'
SE cor. metal base MBT box N 80° W 176.06'
Chiseled "X" cut in top 15" conc. flared end sec. S 69° E 69.25'
On C/L x blacktop N-S & E-W

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9 Standard Kent County Monument
Nail & K.C. remon. tag in N side p. pole S 35° E 91.39'
Nail & K.C. remon. tag in N side p. pole N 70° E 79.47'
Nail & K.C. remon. tag in N side 4" Poplar S 72° W 112.53'
SE cor. metal base MBT box N 80° W 176.06'
Chiseled "X" cut in top 15" conc. flared end sec. S 69° E 69.25'
On C/L x blacktop N-S & E-W



Signed by Randy J. Kolehouse Date 12/1/94
Surveyor's Michigan License No. 25854