

**SURVEY & REMONUMENTATION**

APR 28 1995

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC 29 AM 11:13

KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	<u>L-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*W. J. Bond*  
REG. OF DEEDS

7965

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35								
13													

I, Randy Kolehouse, in a field survey on July 25 19 1994, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-12 This corner was not originally set by the G.L.O.

Date	Survey Records	Williams & Works	Iron
1941-1956	Survey Records	Williams & Works	Iron
1972	L.C.R.C. #180	Williams & Works	1" Iron
1978	L.C.R.C. #1144	Exxel Engineering	Concrete Monument

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-12 Found concrete plat monument per L.C.R.C. #1144 and Exxel Engineering survey records this corner checks Williams & Works measurement to the N 1/4 within 0.5' and to W 1/4 within 1.1' also checks Cascade Office Plaza Subdivision. Concrete monument is 8.8' South and 4.3' West of the intersection of 1/4 lines. Accepted concrete monument as Center Section.


P.A. 345 1990 KENT COUNTY  
PEER APPROVED 11/3/94  
CHAIRMAN Harry Hubert

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-12 Place cap stamped "Kent County Remon." on existing concrete plat monument.

- Nail & K.C. remon. tag in S side 24" Oak N 90° E 29.42'
- Nail & K.C. remon. tag in W side 12" Fir South 14.72'
- Nail & K.C. remon. tag in SE side 12" Maple S 50° W 73.48'
- Nail & K.C. remon. tag in S side 12" Cherry N 80° W 88.14'
- Nail & K.C. remon. tag in SW side 16" Hickory N 25° W 5.03'
- SE cor. concrete bldg. fndn. N 35° W 64.03'



Signed by Randy J. Kolehouse Date 12/12/94  
Surveyor's Michigan License No. 25854