

**SURVEY & REMONUMENTATION**

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970  
 KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 94 DEC -6 AM 9:06

For corners in **COMMISSION**

Kent (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	<u>L-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*W. J. Bond*  
 REG. OF DEEDS

7836

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	6	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on July 25 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

L-13	1831	G.L.O. Notes	L. Lyon	Set Post
	N/A	Wit. Map	K.C. Surveyor	Conc. Mon.
	1972	L.C.R.C. #360	Exxel Engineering	"T" Fence Post
	1982	L.C.R.C. #3164	Williams & Works	Fnd. "T" Post/Set K.C. Mon.
	1991	L.C.R.C. #6374	Marschall	K.C. Monument

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 11/22/82 and was recorded per L.C.R.C. #3164.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

L-13 Found standard Kent County Monument per L.C.R.C. #3164 and set by Williams & Works in place of a "T" fence post they found which was set by Exxel Engineering using Cascadia Meadows Sub. This point checks L.C.R.C. #360.

L.C.R.C. #3164

L.C.R.C. #6374

Nail & K.C. remon. tag in S side triple 16" Ash E 43.75'  
 Nail & K.C. remon. tag in E side 12" Wild Cherry N 10° W 55.42'  
 Nail & K.C. remon. tag S side 4" Oak S 80° W 15.71'  
 Nail & K.C. remon. tag S side 30" Oak N 80° W 33.63'  
 C/L M.H. N 50° E 21.57'

Nail & K.C. remon. tag in S side triple 16" Ash E 43.75'  
 Nail & K.C. remon. tag in E side 12" Wild Cherry N 5° W 55.42'  
 Nail & K.C. remon. tag S side 4" Oak S 85° W 15.71'  
 Nail & K.C. remon. tag S side 30" Oak N 80° W 33.63'  
 C/L M.H. N 50° E 21.57'


The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**L-13 Standard Kent County Monument**

Nail & K.C. remon. tag in S side triple 16" Ash E 43.75'  
 Nail & K.C. remon. tag in E side 12" Wild Cherry N 5° W 55.42'  
 Nail & K.C. remon. tag S side 4" Oak S 85° W 15.71'  
 Nail & K.C. remon. tag S side 30" Oak N 80° W 33.63'  
 C/L M.H. N 50° E 21.57'

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 11/3/94  
 CHAIRMAN W. J. Bond



Signed by Randy J. Kolehouse  
 Surveyor's Michigan License No. 25854

Date 12/1/94