

**SURVEY & REMONUMENTATION**

\$7.00  
\$2.00

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE**

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

DEC 16 AM 9:24

**COMMISSION**

Filing Requirement of Act 74, Mich. P.A. 1970  
Kent County Remonumentation

For corners in

<u>Kent</u> (County)	Located in:	Corner Code #	
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	M-2 (E 1/2 cor, Sec 1)	
	T _____ R _____	(common corner)	
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

*W. J. Glaza*  
REG. OF DEEDS

7884

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, James C. Glaza, in a field survey on December 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

M-2	1831	G.L.O.	Lyon	set post
	No Date	Kent Co. Wit.	-----	iron
	1973	LCRC #525	Bonnema	iron
	1975	LCRC #863	Nederveld	iron
	1982	LCRC #2884	Hackbardt	iron
	1982	LCRC #3094	Jonker	set Kent Co. Monument
	1991	LCRC #6408	Marschall	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 10/12/94  
CHAIRMAN *Harry Hubert*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert Jonker on August 30, 1982 and was recorded per LCRC #3094.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M-2	Found standard Kent Co. Mon. (Harrison) per witnesses from LCRC #3094 as set by Robert Jonker in place of the 1/2" iron he found, and per witnesses from LCRC #6408.		
LCRC #6408			
K.C. remon tag & nail in E side	4" Apple	N15°E	9.11'
K.C. remon tag & nail in W side	14" Oak	S10°W	20.11'
K.C. remon tag & nail in W side	8" Twin Apple	S40°W	29.23'
Nail in face of	20" Oak (broken off 10' high)	West	25.84'
K.C. remon tag & nail in E side	18" Oak	N15°W	41.82'
K.C. remon tag & nail in N side	10" W. Cherry	N75°E	62.28' (3' above ground)
On N-S fence line in line with tree line to West			

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-2	Standard Kent County Monument		
K.C. remon tag & nail in E side	6" Apple	N15°E	9.11'
K.C. remon tag & nail in W side	18" Oak	S10°W	20.11'
K.C. remon tag & nail in W side	8" Twin Apple	S40°W	29.23'
Set K.C. remon tag & nail in N side	12" Twin W. Cherry	N75°E	62.38'
On N-S fence line, in line with tree line to West			

Signed by *James C. Glaza*  
Glaza & Associates, Inc. 40166  
Surveyor's Michigan License No. \_\_\_\_\_

Date December 5, 1994

