

SURVEY & REMONUMENTATION

\$7.00
\$2.00

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Kent County Remonumentation

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94 DEC 16 AM 9:24

Twigg
REG. OF DEEDS

For corners in

Kent (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	M-3 (SE cor, Sec 1) (common corner)
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

7885
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James C. Glaza, in a field survey on December 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-3	1831	G.L.O.	Lyon	set post
	1956	Kent Co. Wit.	-----	iron
	1973	LCRC #525	Bonnema	iron
	1975	LCRC #863	Nederveld	concrete monument
	1977	LCRC #1024	McCloskey	concrete monument
	1979	LCRC #1259	Bonnema	concrete monument
	1981	LCRC #2147	Jonker	set Kent Co. Mon.
	1991	LCRC #6409	Marschall	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert Jonker on August 25, 1981, and was recorded per LCRC #2147.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-3 Found standard Kent Co. Mon. (Harrison) per witnesses from LCRC #2147 as set by Robert Jonker in place of the concrete monument he found, and per witnesses from LCRC #6409.

LCRC #6409	K.C. remon tag & nail in N side 20" Twin W. Cherry	N90°W	14.76'
	K.C. remon tag & nail in E side 22"-14" Twin W. Cherry	N14°E	21.94'
	K.C. remon tag & nail in SE side 6" Oak	S44°W	18.73'
	K.C. remon tag & nail in E side 12" Oak	S17°W	21.58'

At intersection tree row N-S & tree row to West

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3 Standard Kent County Monument	K.C. remon tag & nail in N side 20" Twin W. Cherry	N90°W	14.76'
Set	K.C. remon tag & nail in E side 22"-14" Twin W. Cherry	N14°E	21.95'
	K.C. remon tag & nail in SE side 8" Oak	S44°W	18.73'
	K.C. remon tag & nail in E side 14" Oak	S17°W	21.58'

At intersection tree row N-S & tree to West

P.A. 345 1990 KENT COUNTY

PEER APPROVED *10/12/94*

CHAIRMAN *Darryl Huber*

Date December 5, 1994

Signed by *James C. Glaza*
Glaza & Associates, Inc.

Surveyor's Michigan License No. 40166

