

SURVEY & REMONUMENTATION

APR 28 1995

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

\$7.00
\$2.00

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Kent County Remonumentation

94 DEC 16 AM 9:24

Handwritten Signature
REG. OF DEEDS

For corners in

Kent (County)	Located In:	Corner Code -#
1. Public Land Survey	T 7N R 11W	M-5 (SE cor, Sec 12) (common corner)
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

7887

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James C. Glaza, in a field survey on November 28, 1994
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-5	1831	G.L.O.	Lyon	set post
	1972	Kent Co. Wit.	-----	iron
	1972	LCRC #281	VanKooten	iron
	1972	LCRC #442	VanKooten	iron
	1981	LCRC #2148	Jonker	set Kent Co. Mon.
	1991	LCRC #6411	Marschall	Kent Co. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert Jonker on August 25, 1981 and was recorded per LCRC #2148.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-5 Found standard Kent Co. Mon. (Harrison) per witnesses from LCRC #2148 as set by Rober Jonker in place of a 1" iron he found and per witnesses from LCRC #6411.

LCRC #6411

Nail & tag in W side	30" Maple	N13°E	22.68'
Nail & tag in E side	10" Ash	N15°W	30.46'
Nail & tag in E side	6" Oak	S45°E	7.64'
Nail & tag in s side	12" Aspen	N87°E	32.67'
Nail & tag in SW side	4" W. Cherry	N70°W	16.41'
Nail & tag in E side	4" Oak	S11°E	10.12'
Remains of fence to N-S & W			

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5 Standard Kent County Monument

Nail & K.C. remon tag in W side	30" Maple	N13°E	22.66'
Nail & K.C. remon tag in E side	10" Ash	N15°W	30.46'
Nail & K.C. remon tag in E side	6" Oak	S60°E	7.66'
Nail & K.C. remon tag in S side	12" Aspen	N87°E	32.61'
Nail & K.C. remon tag in SW side	4" W. Cherry	N70°W	16.41'
Nail & K.C. remon tag in E side	4" Oak	S11°E	10.14'
Remains of fence to N-S & W			

P.A. 3-1

PEER APPROVED 10/12/94
CHAIRMAN Harry Hubers

Date December 8, 1994

Signed by James C. Glaza
Glaza & Associates, Inc.

Surveyor's Michigan License No. 40166

