

SURVEY & REMONUMENTATION

\$7.00
\$2.00

APR 28 1995

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970
Kent County Remonumentation

DEC 16 AM 9:24

For corners in **COMMISSION**

Kent (County)	Located In:	Corner Code =#
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	M-6 (E 1/2 cor., Sec 13) (common corner)
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Eric J. Glaza
REG. OF DEEDS

7888

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James C. Glaza, in a field survey on December 2, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-6 1831	G.L.O.	Lyon	set post
1956	Kent Co. Wit.	-----	iron and stone
1977	LCRC #1076	Merdzinski	stone
1982	LCRC #3159	Stadt	set Kent Co. Mon.
1991	LCRC #6417	Marschall	Kent Co. Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Russell E. Stadt on November 22, 1982 and was recorded per LCRC #3159

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6 Found standard Kent Co. Mon. (Harrison) per witnesses from LCRC #3159 as set by Russell E. Stadt in place of a stone he found, and per witnesses from LCRC #6417.

LCRC #6417

K.C. remon tag & nail in NW side 36" Oak	N45°E	18.92'
K.C. remon tag & nail in SW side 12" Oak	N45°W	11.50'
K.C. remon tag & nail in S side 22" Oak	S70°W	42.66'
K.C. remon tag & nail in S side 10" Oak	S70°E	27.13'
K.C. remon tag & nail in W side 12" Oak	S10°W	16.97'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 Standard Kent County Monument:

K.C. remon tag & nail in NW side 36" Oak	N45°E	18.92'
K.C. remon tag & nail in SW side 10" Oak	N45°W	11.53'
K.C. remon tag & nail in S side 22" Oak	S70°W	42.63'
K.C. remon tag & nail in S side 10" Oak	S70°E	27.13'
K.C. remon tag & nail in W side 12" Oak	S10°W	16.97'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 10/12/94

CHAIRMAN Hampshire

Signed by James C. Glaza
Glaza & Associates, Inc.
Surveyor's Michigan License No. 40166

Date December 5, 1994

