

**SURVEY & REMONUMENTATION**

APR 28 1995

\$7.00  
\$2.00

COMMISSION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

DEC 16 AM 9:24

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970  
Kent County Remonumentation

For corners in  
Kent

(County)

Located In:

Corner Code #

- |                                    |   |    |   |     |  |
|------------------------------------|---|----|---|-----|--|
| 1. Public Land Survey              | T | 7N | R | 11W | M-7 (SE cor,<br>Sec 13)<br>(common corner) |
|                                    | T |    | R |     |  |
|                                    | T |    | R |     |  |
|                                    | T |    | R |     |  |
| 2. Property Controlling in Section | S |    | T | R   |  |
|                                    | S |    | T | R   |  |
| 3. Miscellaneous Property in Sec.  | S |    | T | R   |  |
|                                    | S |    | T | R   |  |

*W. J. Bond*  
REG. OF DEEDS

7889

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James C. Glaza, in a field survey on November 25, 1994  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-7	1831	G.L.O.	Lyon	set post
	No Date	Kent Co. Wit.	-----	stake & stones
	1934	W & W	-----	stake & stones
	1967	W & W	-----	C.P. Co. iron & stones
	1985	LCRC #4053	Bonnema	set Kent Co. Mon.
	1991	LCRC #6418	Marschall	Kent Co. Mon.

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented By Douglas W. Bonnema on January 3, 1985 and was recorded per LCRC #4053.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-7 Found standard Kent Co. Mon. (Harrison) per witnesses from LCRC #4053 as set by Douglas W. Bonnema in place of the C.P. Co. iron he found and per witnesses from LCRC #6418.

LCRC #6418

Nail & tag in S side 48" Oak	N20°W	8.38'
Nail & tag in E side 14" Hickory	N10°W	13.67'
Nail & tag in N side 14" Oak	S80°E	33.84'
Nail & tag in W side 14" Oak	S25°E	38.85'
Nail & tag in NW side 8" Oak	S35°W	37.30'
Nail & tag in E side 12" Oak	S45°W	49.23'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7 Standard Kent County Monument

Nail & K.C. remon tag in SW side 36" Oak	N20°W	8.37'
Nail & K.C. remon tag in E side 11" Hickory	N10°W	13.67'
Nail & K.C. remon tag in N side 12" Oak	S80°E	33.82'
Nail & K.C. remon tag in W side 12" Oak	S25°E	38.85'
Nail & K.C. remon tag in NW side 8" Oak	S35°W	37.31'
Set Nail & K.C. remon tag in SE side 12" Oak	S45°W	49.23'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 10/12/94

CHAIRMAN Henry Thubert

Signed by James C. Glaza  
Glaza & Associates, Inc.

Date December 9, 1994

Surveyor's Michigan License No. 40166

