

**SURVEY & REMONUMENTATION**

APR 28 1995

**COMMISSION**

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970  
KENT COUNTY REMONUMENTATION

DEC -6 AM 9:06

For corners in

Kent (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	<u>M-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*W. J. K. [Signature]*  
REG. OF DEEDS

7839

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on July 21 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-10 1831	G.L.O. Notes	L. Lyon	Set Post	P.A. 345 1990 KENT COUNTY
N/A	Wit. Map	K.C. Surveyor	Iron	PEER APPROVED 11/17/94
1971	L.C.R.C. #27	MDSH	1" Pipe	CHAIRMAN <i>[Signature]</i>
1977	L.C.R.C. #1071	Exxel Engineering	3/4" Pipe	
1980	L.C.R.C. #1470	Williams & Works	Fnd. 3/4" Iron in Conc. Mon./Set K.C. Mon.	
1991	L.C.R.C. #6415	Marschall	K.C. Monument	

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 10/30/80 and was recorded per L.C.R.C. #1470.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-10 Found standard Kent County Monument per L.C.R.C.'s #1470 and #6415 as set by Williams & Works in place of a conc. monument (with 3/4" iron) they found which checked L.C.R.C.'s #27 and #1071. This corner is common with A-10 T7N R10W.

L.C.R.C. #1470

- Nail & K.C. remon. tag in NE side p. pole N 50° W 57.50'
- Nail & K.C. remon. tag in S side 6" Box Elder N 65° W 30.10'
- Nail & K.C. remon. tag in E side 8" Oak N 10° E 27.09'
- Nail & K.C. remon. tag in SE side 12" Oak S 40° W 27.43'
- Nail & K.C. remon. tag in W side 14" Oak S 15° W 62.39'
- On North edge of 10' trail running E-W

L.C.R.C. #6415


- Nail & K.C. remon. tag in NE side p. pole N 50° W 57.49'
- Nail & K.C. remon. tag in E side 10" Oak N 10° E 27.03'
- Nail & K.C. remon. tag in SE side 14" Oak S 40° W 27.38'
- Nail & K.C. remon. tag in W side 14" Oak S 15° W 62.37'
- Nail & K.C. remon. tag in S side 8" Hackberry N 75° E 41.92'
- On North edge of 10' trail running E-W

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10 Standard Kent County Monument

- Nail & K.C. remon. tag in NE side p. pole N 50° W 57.49'
- Nail & K.C. remon. tag in E side 10" Oak N 10° E 27.03'
- Nail & K.C. remon. tag in SE side 14" Oak S 40° W 27.38'
- Nail & K.C. remon. tag in W side 14" Oak S 15° W 62.37'
- Nail & K.C. remon. tag in S side 8" Hackberry N 75° E 41.92'
- On North edge of 10' trail running E-W
- C/L E bound M-21 (Fulton Street) 250' more or less



Signed by *[Signature]*

Date 12/1/94

Surveyor's Michigan License No. 25854