

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD

94 DEC -6 AM 9:06

For corners in

<u>Kent</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>11W</u>	<u>M-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Lucy Bond
 REG. OF DEEDS

7840

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on July 19 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 M-11 1831 G.L.O. Notes L. Lyon Set Post

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 11/17/94
 CHAIRMAN *Randy Kolehouse*

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Maurice J. Rosema on 6/25/84 and was recorded per L.C.R.C. #3869. This corner is common with A-11 T7N R10W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 M-11 Found standard Kent County Monument per L.C.R.C.'s #3869 and #6414 as set by M. Rosema in place of a 3/4" iron at a fence corner N-S & W he found which checked L.C.R.C. #3269.

L.C.R.C. #3869	L.C.R.C. #6414
Nail & remon. tag in NE side dbl. 18" Oak N 52° W 27.58'	Nail & tag NE side twin 22" Oak N 50° W 27.64'
	Nail & tag W side twin 22" Oak N 25° W 33.33'
	Nail & tag S side 40" Maple N 89° W 34.29'
	Nail & tag N side 6" Ash N 90° W 4.75'
	Nail & tag W side 10" Oak S 15° E 21.11'
	Corner is at remains of fence N-W and to West

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 A-11 Standard Kent County Monument
 Nail & K.C. remon. tag NE side twin 22" Oak N 50° W 27.64'
 Nail & K.C. remon. tag W side twin 22" Oak N 25° W 33.33'
 Nail & K.C. remon. tag S side 40" Maple N 89° W 34.29'
 Nail & K.C. remon. tag N side 6" Ash N 90° W 4.75'
 Nail & K.C. remon. tag W side 10" Oak S 15° E 21.11'
 Corner is at remains of fence N-W and to West



igned by *Randy J. Kolehouse* Date 12/1/94
 urveyor's Michigan License No. 25854