

# SURVEY & REMONUMENTATION

APR 28 1995

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
94 NOV 28 AM 11:42

*Luigi J. Bond*  
REG. OF DEEDS

7273

Register of Deeds Stamp & File Number

For corners in  
KENT COUNTY  
(County)

Located In:

Corner Code -##

- |                                    |                          |            |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey              | T <u>7N</u> R <u>12W</u> | <u>A-6</u> |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Byl, in a field survey on July 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- |     |         |                      |            |                                       |
|-----|---------|----------------------|------------|---------------------------------------|
| A-6 | 1836    | GLO                  | Brookfield | Set Post (common with M-6, T7N, R13W) |
|     | 1911-54 | Williams & Works     |            | Stake-Stone-Iron                      |
|     | 1924    | "Fairview Park" plat | Christ     | Iron Pipe                             |
|     | 1927    | Kent Co. Wit.        |            | No desc. of corner-witnesses given    |
|     | 1985    | LCRC #4254           | Byl        | Set Kent County Monument              |
|     | 1990    | LCRC #5500           | Starr      | Kent County Monument                  |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 5/20/85 and was recorded per LCRC #4254.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by William R. Byl in place of the Iron Pipe he found. Said Iron Pipe checks with Williams & Works information and dimensions from "Fairview Park."

LCRC #4254

Nail & tag 6" Oak S45°W 10.57'  
Nail & tag 24" Quad Aspen N30°W 38.24'

LCRC #5500

Nail & KC tag 6" Oak S45°W 10.57'  
Nail & KC tag 24" Quad Aspen N30°W 38.24'  
Nail & KC tag 6" Poplar West 5.32'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6 Standard Kent County Monument

- |   |       |        |
|---|-------|--------|
| Nail & KC Remon. tag E. side 8" Oak                     | S45°W | 10.57' |
| Nail & KC Remon. tag E. side 27" Quad Aspen             | N30°W | 38.24' |
| Nail & KC Remon. tag N. side 8" Poplar                  | S90°W | 5.32'  |
| On fence line and tree line to West; On field line East |       |        |

P.A. 345 1990 KENT COUNTY

PEER APPROVED 11/17/94

CHAIRMAN Harry Huber



Signed by William R. Byl Date 11-17-94

Surveyor's Michigan License No. 23502