

SURVEY & REMONUMENTATION

APR 28 1995

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:

Corner Code -#

- | | | |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>7N</u> R <u>12W</u> | <u>A-7</u> |
| | T _____ R _____ | _____ |
| | / T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
94 NOV 28 AM 11:42

Lucy Bond
REG. OF DEEDS

7274

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William R. Byl, in a field survey on July 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-7	1836	GLO	Brookfield	Set Post (common with M-7, T7N, R13W)
	1935	Kent Co. Wit		Iron
	1981	LCRC #1844	Shangraw	Set Kent County Monument
	1990	LCRC #5501	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Carl F. Shangraw on 5/26/81 and was recorded per LCRC #1844.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Carl F. Shangraw in place of the 1/2" Iron over the Boat Spike of the 3/4" Iron he found. Said Irons check with Kent Co. Wit. and survey information by others.

LCRC #1844

KC Nail & tag 34" Ash	S40°W	40.50'
KC Nail & tag T. Pole	N47°W	43.43'
KC Nail & tag 12" Ash	S85°E	94.70'
Face gas line marker	N16°E	29.35'

LCRC #5501

Nail & KC tag 36" Ash	S40°W	40.77'
Nail & KC tag Tele. Pole	N55°W	43.43'
Nail & KC tag 14" Ash	S75°E	94.11'
Face of gas line marker	N30°E	29.40'

C/L of E-W Bit. Rd. is 1' North

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


A-7 Standard Kent County Monument

New Nail & KC Remon. tag W. side 36" Ash	S40°W	40.75'
Nail & KC Remon. tag N. side Tele. Pole	N55°W	43.43'
New Nail & KC Remon. tag N. side 14" Ash	S75°E	94.19'
Face of gas line marker	N30°E	29.40'

C/L of E-W Bit. Rd. is 1' North P.A. 345 1990 KENT COUNTY

PEER APPROVED 11/17/94

CHAIRMAN *[Signature]*



Signed by *[Signature]* Date 11-17-94

Surveyor's Michigan License No. 23502