

# SURVEY & REMONUMENTATION

APR 28 1995

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
94 NOV 28 AM 11:46

For corners in  
KENT COUNTY  
(County)

Located In: Corner Code-#

- |                                    |                          |             |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey              | T <u>7N</u> R <u>12W</u> | <u>C-10</u> |
|                                    | T _____ R _____          | _____       |
|                                    | T _____ R _____          | _____       |
|                                    | T _____ R _____          | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____       |
|                                    | S _____ T _____ R _____  | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____       |
|                                    | S _____ T _____ R _____  | _____       |

*Lucy Bond*  
REG. OF DEEDS

7294

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William R. Byl, in a field survey on July 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

C-10	1837	GLO	Whitcomb	Set Post
		Kent Co. Wit.		Iron & Stone
	1978	LCRC #1213	Bonnema	1/2" Iron
	1981	LCRC #2040	Hackbardt	Set Kent County Monument
	1990	LCRC #5522	Starr	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 11/17/94  
CHAIRMAN Harvey Hubert

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Glen S. Hackbardt on 6/9/81 and was recorded per LCRC #2040

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-10 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Glen S. Hackbardt in place of the 1/2" Iron he found. Said 1/2" Iron checks with Kent Co. Wit., LCRC #1213 and survey information by others.

LCRC #2040				LCRC #5522			
KC Nail & tag CP Pole	N45°E	86.68'		Nail & KC Remon. tag CP Pole	N45°E	86.68'	
KC Nail & tag 10" Cherry	South	22.57'		Nail & KC Remon. tag 10" Cherry	South	22.57'	
KC Nail & tag 5" Ash	S30°W	34.67'		Nail & KC Remon. tag 5" Ash	S30°W	34.67'	
KC Nail & tag 15" Oak	S60°W	30.52'		Nail & KC Remon. tag 15" Oak	S60°W	30.52'	
				On tree line S-W			

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-10 Standard Kent County Monument			
New Nail & KC Remon. tag W. side CP Pole	N45°E	86.68'	
Nail & KC Remon. tag E. side 12" Cherry	S00°E	22.57'	
New Nail & KC Remon. tag E. side 8" Ash	S30°W	34.67'	
New Nail & KC Remon. tag E. side 15" Oak stump	S60°W	30.55'	
Set Nail & KC Remon. tag NE side 10" Oak	S35°E	25.38'	
On tree line S-W			



Signed by *William R. Byl*  
Surveyor's Michigan License No. 23502

Date 11-17-94