

SURVEY & REMONUMENTATION

APR 28 1995

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
94 NOV 28 AM 11:46

COMMISSION

For corners in
KENT COUNTY
(County)

Located In: Corner Code-##

1. Public Land Survey	T 7N R 12W	C-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

W. J. Bond
REG. OF DEEDS

7295

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, William R. Byl, in a field survey on July 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-11	1837	GLO	Whitcomb	Set Post
	1935, 1949	Kent Co. Wit.		1/2" Iron-Mon. Box
	1973	LCRC #394	Spicer	Mon. Box
	1980	LCRC #1450	Merdzinski	Set Kent County Monument
	1990	LCRC #5523	Starr	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 11/17/94
CHAIRMAN *W. J. Bond*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 10/27/80 and was recorded per LCRC #1450

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1 1/2" Iron in Mon. Box he found. Said 1 1/2" Iron in Mon. Box checks with Kent Co. Wit. and LCRC #394

<u>LCRC #1450</u>		<u>LCRC #5523</u>	
Nail & tag 24" Hickory	N70°W 98.52'	Nail & KC Remon. tag 24" Hickory	N70°W 98.52'
Nail & tag 24" Hickory	N20°W 42.18'	Nail & KC Remon. tag 24" Hickory	N20°W 42.18'
Nail & tag CP Pole	N10°E 76.85'	Nail & KC Remon. tag CP Pole	N10°E 76.85'
Nail & tag 12" Hickory in group of 5 trees	S50°E 64.10'	Nail & KC Remon. tag 12" Hickory in group of 5 trees	S57°E 64.00'
NW cor. hse. #3980 fdn.	S15°E 114.63'	NW cor. hse. #3980 fdn.	S15°E 114.63'
SW cor. hse. #3975 fdn.	N60°E 169.90'	SW cor. hse. #3975 fdn.	N60°E 169.60'
C/L BT 1.5' South		C/L E-W Bit. Rd. os 1.5' South	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11 Standard Kent County Monument	
New Nail & KC Remon. tag S. side 24" Hickory	N70°W 98.52'
New Nail & KC Remon. tag W. side 24" Hickory	N20°W 42.15'
Nail & KC Remon. tag E. side CP Pole	N10°E 76.89'
Nail & KC Remon. tag N. side 12" Hickory in group of 5 trees	S57°E 64.04'
NW cor. hse. #3980 fdn.	S15°E 114.63'
SW cor. hse. #3975 fdn.	N60°E 169.60'
C/L E-W Bit. Rd. os 1.5' South	

Signed by *W. R. Byl*
Surveyor's Michigan License No. 23502

Date 11-17-94

