

\$7.00
\$2.00

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

PLS

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey	T	7N	R	12W	D-4
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

REG. OF DEEDS

Handwritten signature

95 DEC 26 PM 12:42

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

8840

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Dec. 15, 1994,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-4	1837	GLO	Not Set
	1928	Williams & Works	Intersected 1/4 lines for Center
	1946-66	Williams & Works	Retraced 1928 survey-set Iron & Stones
			3' S. of fence W., 14' S. of fence E., 5' W. of fence N., Iron 14' N.
		Kent Co. Wit.	Iron

P.A. 345 1990 KENT COUNTY

PEER APPROVED: 12/15/94

CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-4 Location of Central 1/4 corner of Section 8 is in a swamp area with 2'- 4' standing water. Research of surveys and adjoining plats coupled with measurements and bearings indicates all have used an intersection of 1/4 lines for Central 1/4 corner (per Williams & Works-1928). Did not look for or tie in any existing monumentation at Central 1/4 corner or see any practical reason to monument said location. See LCRC's for location of reference monuments set on the E-W 1/4 line.

The intersection of the 1/4 lines is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-4 NO MONUMENT SET AT THIS CORNER

See LCRC # 8841 for location of witness monument



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 12/14/95