

\$7.00
\$2.00

JAN 24 1996

KENT COUNTY REMONUMENTATION

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey	T	7N	R	12W	D-6
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous	S		T	R	
Property in Section	S		T	R	

REG. OF DEEDS

Lucy Standa

95 DEC 26 PM 12:42

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

8851

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Nov. 15, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- D-6 1837 GLO Not Set
- 1903-41 Williams & Works Iron
- 1935 Kent Co. Wit. Iron
- Fc. N. 32' Iron S. 177.65' C/L Pvmnt. SW 70.1'
- 1941-62 Williams & Works Iron next to CP Mon. on N-S 1/4 line, 6.78' S. of true
- 1975 LCRC #816 Spicer Capped Iron (CP Co.)
- W. side CP Iron S. 30.25' Iron W. 32.0'
- CP Iron S45°E 8.75' 6" Maple S50°W 14.84'
- Exxel Eng. Used per LCRC #816 (1.0'± E. & 6.8'± S. of true "X")

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-6 Found Capped Iron (CP Co.) next to CP Co. post that fits remaining witnesses of those above. Said Capped Iron is 7.0' S. & 0.8' E. from true intersection of 1/4 lines and fits measurements of others.

The Capped Iron is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 11/17/94
CHAIRMAN *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-6 Set Standard Kent County Monument in place of the Capped Iron.
- Top C/L CP post S90°W 32.30'
- Set Nail & KC Remon. tag SE side 16" Maple S50°W 14.89'
- Top C/L CP post N00°E 32.94'
- Set Nail & KC Remon. tag W. side 12" Oak S25°E 27.16'
- Set Nail & KC Remon. tag S. side 10" Oak S70°E 17.57'
- Set Nail & KC Remon. tag E. side 12" Elm N25°E 34.13'



Signed by *[Signature]*
Surveyor's Michigan License No. 30077

Date 12/14/95