

SURVEY & REMONUMENTATION

APR 28 1995

KENT COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
94 DEC 27 AM 9:04

W. R. Byl
REG. OF DEEDS

For corners in
KENT COUNTY

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>12W</u>	D-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

7893

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, William R. Byl, in a field survey on July 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-11	1837	GLO	Whitcomb	Set Post
	1949	Kent Co. Wit.		Iron (Mon. Box)
	1974	LCRC #684	Bonnema	2" Iron in Mon. Box
	1991	LCRC #5864	Bueche	Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 12/22/94
CHAIRMAN *W. R. Byl*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group. (No record of or LCRC recorded of who set Kent Co. Monument and when).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as found by John C. Bueche. Said location of Kent Co. Mon. checks with Kent Co. Wit. and LCRC #684.

LCRC #5864

Nail & Remon. tag W. side Light Pole	S10°E	23.23'
Nail & Remon. tag E. side 14" Elm	S50°W	68.02'
Nail & Remon. tag SE side P. Pole	N60°E	98.86'
SW cor. back of hood of CB	N20°W	44.98'
On C/L blacktop E-W & N.		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>D-11 Standard Kent County Monument</u>		
Nail & KC Remon. tag W. side Light Pole	S10°E	23.16'
New Nail & KC Remon. tag E. side 14" Elm	S50°W	67.88'
Nail & KC Remon. tag SE side P. Pole	N60°E	98.89'
SW cor. back of hood of CB	N20°W	44.98'
On C/L blacktop E-W & N.		



Signed by *W. R. Byl*
Surveyor's Michigan License No. 23502

Date 12/07/94