

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94 NOV 28 AM 11:46

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 7N R 12W D-13
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Glen S. Hackbardt
REG. OF DEEDS

7302

Register of Deeds Stamp & File Number

I, William R. Byl, in a field survey on May 3, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-13	1837	GLO	Brookfield	Set Post
		Kent Co. Wit.		Iron
	1981	LCRC #2026	Hackbardt	Set Kent County Monument
	1990	LCRC #5530	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Glen S. Hackbardt on 8/24/81 and was recorded per LCRC #2026

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Glen S. Hackbardt in place of the 1/2" Iron he found. Said 1/2" Iron checks with Kent Co. Wit.

LCRC #2026	LCRC #5530
KC Nail in tag 4" Oak South 23.30'	Nail & KC Remon. tag 4" Oak S10°W 23.45'
KC Nail in tag 4" Maple N85°W 46.33'	Nail & KC Remon. tag 4" Maple N85°W 46.30'
KC Nail in tag 12" Oak N05°W 66.65'	Nail & KC Remon. tag 12" Oak N05°W 66.60'
KC Nail in tag 6" Oak N40°E 32.98'	Nail & KC Remon. tag 6" Oak N40°E 32.95'
	On tree and fence line E-W-N

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 Standard Kent County Monument

New Nail & KC Remon. tag W. side 8" Oak	S10°W	23.49'
New Nail & KC Remon. tag S. side 6" Maple	N85°W	46.28'
Nail & KC Remon. tag W. side 18" Oak	N05°W	66.65'
Nail & KC Remon. tag S. side 10" Oak	N40°E	32.95'
On tree and fence line E-W-N		

P.A. 345 1990 KENT COUNTY

PEER APPROVED 11/17/94

CHAIRMAN Glen S. Hackbardt



Signed by W. R. Byl Date 11-17-94
Surveyor's Michigan License No. 23502