

SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94 NOV 28 AM 11:46

For corners in **COMMISSION**
KENT COUNTY

(County)	Located In:	Corner Code #/
1. Public Land Survey	T <u>7N</u> R <u>12W</u>	<u>E-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

W. R. Byl
REG. OF DEEDS

7303

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William R. Byl, in a field survey on Aug. 24, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1	1837	GLO	Brookfield	Set Post
	1971	LCRC #65	Spicer	1 1/4" Iron
	1982	LCRC #3154	Hackbardt	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Glen S. Hackbardt on 8/2/82 and was recorded per LCRC #3154

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Glen S. Hackbardt on Township line in place of the 1 1/4" Iron he found that was next to a 10" x 24" cylindrical stone. Said 1 1/4" Iron checks with LCRC #65.

LCRC #3154

KC Nail & tag CP Pole	S20°W	53.45'
KC Nail & tag CP Pole	N20°W	83.73'
KC Nail & tag CP Pole	N30°E	59.73'
Harrison Monument	East	34.30'
NE cor. (blk porch)	S30°E	118.08'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 4/17/94

CHAIRMAN *Harry Hubers*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1 Standard Kent County Monument		
KC Nail & tag E. side CP Pole	S20°W	53.39'
KC Nail & tag W. side CP Pole	N20°W	84.25'
KC Nail & tag W. side CP Pole (diff. pole)	N30°E	62.60'
KC Monument (E-13, T8N, R12W)	S90°E	34.30'
NE cor. (block porch)	S30°E	117.96'



Signed by *W. R. Byl*
Surveyor's Michigan License No. 23502

Date 11-17-94