

SURVEY & REMONUMENTATION

APR 28 1995

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

NOV 28 AM 11:47

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 7N R 12W
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

E-11

W. R. Byl
REG. OF DEEDS

7312

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Byl, in a field survey on July 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-11	1837	GLO	Whitcomb	Set Post
	1940	Kent Co. Wit.		Conc. Mon.
	1977	LCRC #1033	Merdzinski	3" Iron in Mon. Box
	1982	LCRC #3315	Tobin	Set Kent County Monument
	1990	LCRC #5540	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Douglas J. Tobin on 5/21/82 and was recorded per LCRC #3315

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Douglas J. Tobin in place of the 3" Pipe he found in a Mon. Box. Said 3" Pipe checks with Kent Co. Wit. and LCRC #1033.

LCRC #3315

KC Nail & tag MBT Pole S50°W 48.20'

KC Nail & tag MBT Pole N50°W 56.20'

KC Nail & tag Lt. Pole South 24.62'

KC Nail & tag 12" Maple N60°E 74.20'

LCRC #5540

Nail & KC Remon. tag MBT Pole S50°W 48.20'

Nail & KC Remon. tag MBT Pole N50°W 56.70'

Nail & KC Remon. tag Lt. Pole South 24.62'

Nail & KC Remon. tag 12" Maple N60°E 74.20'

Nail & CK Remon. tag 12" Pine N25°E 63.19'

On C/L Bit. Rd. N-E-W; On tree row S.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11 Standard Kent County Monument

Nail & KC Remon. tag N. side MBT Pole S50°W 48.22'

Nail & KC Remon. tag NE side MBT Pole N50°W 56.73'

Nail & KC Remon. tag W. side Lt. Pole S00°E 24.63'

New Nail & KC Remon. tag S. side 12" Maple N60°E 74.03'

Set Nail & KC Remon. tag NW side 14" Pine N40°E 53.29'

On C/L Bit. Rd. N-E-W; On tree row S.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 11/17/94
CHAIRMAN Henry G. Gabe

Signed by W. R. Byl Date 11-17-94
Surveyor's Michigan License No. 23502