

SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94 NOV 28 AM 11:47

For corners in **COMMISSION**
KENT COUNTY
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>12W</u>	<u>G-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Lucy Bond
REG. OF DEEDS

7319

Register of Deeds Stamp & File Number

I, William R. Byl, in a field survey on June 30, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

P.A. 345 1990 KENT COUNTY
PEER APPROVED 11/17/94
CHAIRMAN *[Signature]*

G-2	1837	GLO	Whitcomb	Set Post
	1960	Kent Co. Wit.	MDSH	1" Iron
	1980	LCRC #1352	Bonnema	1" Iron
	1981	LCRC #1853	Tobin	Set Kent County Monument
	1990	LCRC #5549	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Douglas J. Tobin on 2/26/81 and was recorded per LCRC #1853

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-2 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Douglas J. Tobin in place of the 1" Iron he found. Said 1" Iron checks with Kent Co. Wit. and LCRC #1352

LCRC #1853				LCRC #5549			
KC Nail & tag Tw. 20" Cherry	West	15.87'		Nail & KC tag 26" W. Cherry	West	15.90'	
SW cor. hse. fnd.	N75°W	62.24'		Nail & KC tag 28" Maple	N20°E	11.98'	
KC Nail & tag 28" Maple	N25°E	11.05'		Nail & KC tag 16" W. Cherry	S45°E	13.46'	
KC Nail & tag 14" Cherry	S45°E	13.51'		SW cor. house foundation	N50°W	62.30'	
				On tree row N-S-E-W			

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-2 Standard Kent County Monument			
New Nail & KC Remon. tag N. side 28" W. Cherry	S90°W	15.87'	
Nail & KC Remon. tag E. side 30" Maple	N20°E	11.98'	
New Nail & KC Remon. tag N. side 18" W. Cherry	S45°E	13.47'	
SW cor. house foundation	N50°W	62.32'	
On tree row N-S-E-W			



Signed by *W. R. Byl* Date 11-17-94
Surveyor's Michigan License No. 23502