

**SURVEY & REMONUMENTATION**

KENT COUNTY REMONUMENTATION

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

9 1/2 NOV 28 AM 11:47

For corners in **COMMISSION**  
KENT COUNTY  
(County)

Located In: Corner Code =#

1. Public Land Survey	T	7N	R	12W	G-5
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

*Lucy J. Bond*  
REG. OF DEEDS

7322

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William R. Bvl, in a field survey on June 30, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G-5	1837	GLO	Whitcomb	Set Post
	1956	Kent Co. Wit.		Leaded Stone
	1973	LCRC #468	Spicer	"T" Iron
	1982	LCRC #2790	Merdzinski	Set Kent County Monument
	1990	LCRC #5552	Starr	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 11/17/94  
CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 3/24/82 and was recorded per LCRC #2790

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-5 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the "T" Iron he found. Said "T" Iron checks with Kent Co. Wit. and LCRC #468.

LCRC #2790		LCRC #5552	
Nail & KC tag 34" Oak	S25°E 98.50'	Nail & KC Remon. tag 34" Oak	S25°E 98.50'
Nail & KC tag P. Pole	N45°W 28.40'	Nail & KC Remon. tag P. Pole	N45°W 28.40'
Nail & KC tag P. Pole	N15°E 71.72'	Nail & KC Remon. tag 8" Pine	N70°E 42.00'
Nail & KC tag 8" Pine	N70°E 42.00'	Nail & KC Remon. tag P. Pole	N20°E 73.20'
Top centerline hydrant	S82°W 20.83'	Top centerline hydrant	S82°W 20.83'
W. edge manhole rim	East 3.49'	W. edge of manhole rim	East 3.49'

Corner is on C/L Oakleigh Ave. N-S On C/L Oakleigh Ave. N-S; On fence line East  
The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5 Standard Kent County Monument	
New Nail & KC Remon. tag W. side 36" Oak	S25°E 98.46'
Nail & KC Remon. tag NE side P. Pole	N45°W 28.42'
Nail & KC Remon. tag E. side P. Pole	N20°E 73.22'
Set Nail & KC Remon. tag NW side 18" Maple	N50°E 27.66'
Top centerline hydrant	S82°W 20.83'
W. edge manhole rim	S90°E 3.49'
Corner is on C/L Oakleigh Ave. N-S	
On fence line East	



Signed by *W. R. Bvl*  
Surveyor's Michigan License No. 23502

Date 11-17-94