

SURVEY & REMONUMENTATION

APR 28 1995

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94 DEC -5 AM 8:52

COMMISSION

For corners in
KENT COUNTY
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>12W</u>	<u>G-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

W. R. Bysl
REG. OF DEEDS

7592

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Bysl, in a field survey on Nov. 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-12	1837	GLO	Whitcomb	Set Post
	1986-1940	Williams & Works		Stone with copper plug
		Kent Co. Wit.		Leaded Stone
	1983	LCRC #3301	Glaza	Brass plug in stone
	1984	LCRC #3856	Kolehouse	Set Kent County Monument
	1990	LCRC #5559	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 6/23/84 and was recorded per LCRC #3856

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-12 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the Stone with copper plug he found. Said Stone checks with Williams & Works and LCRC #3301.

LCRC #3856

LCRC #5559

Nail & KC Remon. tag N. side 10" Sassafrass East	7.70'	same witnesses as LCRC #3856
Nail & KC Remon. tag E. side 12" Oak	N10°E 6.90'	
Nail & KC Remon. tag W. side 24" Oak	N05°W 16.50'	
Nail & KC Remon. tag S. side 6" Oak	West 13.11'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12 Standard Kent County Monument

New Nail & KC Remon. tag N. side 10" Sassafrass	S90°E	7.70'
Nail & KC Remon. tag E. side 12" Oak (dead)	N10°E	6.90'
New Nail & KC Remon. tag W. side 24" Oak	N05°W	16.48'
New Nail & KC Remon. tag S. side 9" Oak	S90°W	12.96'
Set Nail & KC Remon. tag SW side 6" Maple	S40°E	20.61'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 12/1/94

CHAIRMAN Randy Kolehouse



Signed by W. R. Bysl
Surveyor's Michigan License No. 23502

Date 112794