

**SURVEY & REMONUMENTATION**

KENT COUNTY REMONUMENTATION

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

94 NOV 26 AM 11:48

**COMMISSION**

For corners in  
KENT COUNTY  
(County)

Located In: Corner Code #

- |                                    |                          |            |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey              | T <u>7N</u> R <u>12W</u> | <u>H-3</u> |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |

*W. J. Bond*  
REG. OF DEEDS

7329

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William R. Byl, in a field survey on May 27, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

H-3	1837	GLO	Whitcomb	Set Post
	1960	Kent Co. Wit.	MDSH	3/4" Iron in mon. box
	1974	LCRC #628	South	1" Pipe in mon. box
	1974	LCRC #753	Spicer	3/4" Iron in mon. box
	1981	LCRC #1852	Tobin	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Douglas J. Tobin and was recorded per LCRC #1852

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-3 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Douglas J. Tobin in place of the 3/4" Iron he found in a mon. box. Said 3/4" Iron in mon. box checks with Kent Co. Wit. and LCRC's #628 & #753.

LCRC #1852

Nail & tag SW side MBT pole	S45°E	81.26'
Nail & tag SE side wood fence post	S35°W	59.27'
Nail & tag E. side 16" Poplar	N20°W	46.21'
Nail & tag E. side 26" Oak	N05°W	66.7'

P.A. 345 1980 KENT COUNTY

PEER APPROVED 11/17/94  
CHAIRMAN *Harry Stupine*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-3 Standard Kent County Monument in gravel shoulder		
Nail & KC Remon. tag SE side wood fence post	S35°W	59.56'
New Nail & KC Remon. tag E. side 20" Poplar	N20°W	46.28'
New Nail & KC Remon. tag E. side 30" Oak	N05°W	66.79'
Set Nail & KC Remon. tag NW side P. Pole	S30°W	34.63'
PK in C/L 3 Mile Rd.	N00°E	17.27'



Signed by *W. R. Byl*  
Surveyor's Michigan License No. 23502

Date 11-17-94