

APR 28 1995

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

94 NOV 26 AM 11:48

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

Located in:

Corner Code #

1. Public Land Survey	T	<u>7N</u>	R	<u>12W</u>	H-5
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

*W. R. Gyl*  
REG. OF DEEDS

7330

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William R. Gyl, in a field survey on May 27, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

H-5	1837	GLO	Whitcomb	Set Post
	1939	Kent Co. Wit		3/4" Iron
	1981	LCRC #1851	Tobin	Set Kent County Monument
	1985	LCRC #4155	Chettleburgh	Reset Kent County Monument after road construction

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 11/17/94  
CHAIRMAN *Thomas W. Chettleburgh*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Douglas J. Tobin on 6/10/81 and was recorded per LCRC #1851 and Kent Co. Mon. in place of broken Kent Co. Mon. by Thomas W. Chettleburgh on 4/3/85 and was recorded per LCRC #4155.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-5 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as reset by Thomas W. Chettleburgh. 3/4" Iron as found by Douglas J. Tobin prior to first setting of Kent Co. Mon. checked with Kent Co. Wit., previous surveys, and unrecorded witnesses by others.

<u>LCRC #1851</u>		<u>LCRC #4155</u>	
3/4" Iron	N35°W 6.95'	Nail W. sd. 13" Elm	N13°E 151.60'
KC nail-tag W. sd. 10" Elm	S25°W 42.57'	Nail NW sd. Tri. 10" Maple	N39°E 150.25'
Nail in E. sd. 5" Box Elder	N10°W 29.18'	Nail S. sd. P. Pole	S89°E 108.98'
SW bolt 1.5' x 1.5' conc. base of RR		Nail N. sd. P. Pole	N86°W 258.71'
crossing flasher	N25°E 98.23'	Nail NE sd. Tri. 16" Cottonwood	N50°W 227.01'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5 Standard Kent County Monument	
Nail & KC Remon. tag NW sd. Tri. 14" Maple	N39°E 150.25'
Nail & KC Remon. tag S. sd. P. Pole	S89°E 108.98'
Nail & KC Remon. tag N. sd. P. Pole	N86°W 258.71'
C/L NW bolt at N. end railing E. sd. of bridge	S10°W 46.73'
E. face of curb	W'ly 8.60'
Set Nail & KC Remon. tag SE sd. P. Pole	N65°E 17.78'
C/L Water manhole	N30°E 27.03'



Signed by *W. R. Gyl* Date 11-17-94

Surveyor's Michigan License No. 23502