

\$7.00
\$2.00

JAN 24 1996

KENT COUNTY REMONUMENTATION

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey	T	7N	R	12W	H-10
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		
	S		T		
3. Miscellaneous	S		T		
Property in Section	S		T		

REG. OF DEEDS

8861

Register of Deeds Stamp & File Number

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
95 DEC 26 PM 12:43

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on Nov. 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-10	1837	GLO	Not Set
	1896-1958	Williams & Works	No desc. of corner - Gas Pipe - Iron
		40" Oak W. 40.90'	16" Elm NE 57.0'
		12" Elm SE 66.50'	8" Elm SSE 57.15'
	1941-50	Kent Co. Wit.	Iron
		10" Elm SE 57.1'	18" Elm NE 56.8'
		C/L hydr. NE 42.20'	12" Elm SSE 66.3'
			20" Elm ESE 56.10'
	1979	LCRC #1258 Bonnema	3/4" Iron
		32" Oak W. 79.18'	P.P. NW 48.33'
			P.P. ENE 52.75'
			C/L hydr. NE 41.23'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-10 Found 3/4" Iron Pipe that fits remaining witnesses of those above. Said Iron Pipe is 26.9' S. & 0.4' W. from true intersection of 1/4 lines and agrees with previous survey data of others.

The 3/4" Iron Pipe is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 11/17/94

CHAIRMAN [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-10	Set Standard Kent County Monument in place of 3/4" Iron Pipe
	SE face of gas vent pipe N35°W 50.28'
	C/L top fire hydrant N35°E 41.27'
	NW corner brick house #1959 N40°E 106.47'
	Nail & MDSH tag S. side P. Pole N70°E 52.71'
	SW corner brick house #1958 S35°E 122.57'
	C/L manhole S00°W 10.30'



Signed by

[Signature]

Date

12/14/95

Surveyor's Michigan License No.

30077