

SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

94 NOV 28 AM 11:48

COMMISSION

For corners in
KENT COUNTY

(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|-----------|---|------------|-------------|
| 1. Public Land Survey | T | <u>7N</u> | R | <u>12W</u> | <u>H-13</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

W. R. Byl
REG. OF DEEDS

7334

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William R. Byl, in a field survey on June 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13	1836	GLO	Brookfield	Set Post
	1883	Williams & Works		Stake
	1885	City of Grand Rapids		Set City Iron
	1971	LCRC #66	Spicer	Conc. Mon.
	1985	LCRC #4131	Byl	Set Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 11/17/94
CHAIRMAN *Harry Hubers*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 1/8/85 and was recorded per LCRC #4131.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 Found Rerod and Cap (Nederveld) over remains of standard Kent Co. Mon. (Harrison) 36" deep per witnesses from above LCRC as set by William R. Byl in place of the City Iron with stones and crockery around, which he found. Said City Iron checks with dimensions of 1885 triangulation survey of the Grand River. LCRC #66 may be mislabeled and is for another corner???

LCRC #4131: Nail & tag E. side 18" Maple S00°W 36.08'
Nail & tag S. side 30" Maple S55°E 15.49'
Nail & tag N. side 24" Maple N60°E 59.86'
Nail & tag E. side 18" Basswood N35°W 90.68'
Nail & tag S. side 24" Basswood S90°W 84.28'
Corner is in E. shoulder of Veterans Memorial Dr.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 Set Standard Kent County Monument in place of rerod and cap over remains of broken Kent County Monument.

New Nail & KC Remon. tag E. side 22" Maple	S00°W	36.08'
New Nail & KC Remon. tag S. side 33" Maple	S55°E	15.29'
New Nail & KC Remon. tag N. side 28" Maple	N60°E	59.73'
Nail & KC Remon. tag E. side 22" Basswood	N35°W	90.60'
Set Nail & KC Remon. tag N. side 12" Basswood	N80°W	80.55'
C/L Kent Trails Bike Path (asphalt)	NW'y	12' m/1



Signed by *W. R. Byl* Date 11-17-94
Surveyor's Michigan License No. 23502