

SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 NOV 28 AM 11:48

COMMISSION

For corners in
KENT COUNTY

(County)	Located In:	Corner Code #/
1. Public Land Survey	T <u>7N</u> R <u>12W</u>	<u>I-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

W. R. Byl
REG. OF DEEDS

7335

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, William R. Byl, in a field survey on July 27, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-1	1837	GLO	Brookfield	Set Post
	1944, 1956	Kent Co. Wit.		Stone & Iron
	1981	LCRC #1839	Hackbardt	Set Kent County Monument
	1990	LCRC #5436	Starr	Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 11/17/94
CHAIRMAN W. R. Byl

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Glen S. Hackbardt on 3/31/81 and was recorded per LCRC #1839

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Glen S. Hackbardt 0.72' North of the 1 1/2" Iron he found. Said 1 1/2" Iron checks with Kent Co. Wit. and previous survey information by others.

LCRC #1839		LCRC #5436	
Nail in 16" Apple	North 103.50'	Nail & KC Remon. tag Lt. Pole	N50°W 42.35'
Harrison Mon.	West 64.85'	Nail & KC Remon. tag P. Pole	S30°E 64.29'
KC Nail & tag CP	S45°W 66.16'	Nail & KC Remon. tag P. Pole	S40°W 65.83'
C/L Manhole	S15°E 43.20'	KC Mon.	West 64.81'
KC Nail & tag CP	S40°E 64.39'	On C/L E-W-S Bit. Rd.	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 Standard Kent County Monument	
Nail & KC Remon. tag S. side Lt. Pole (new location)	N50°W 43.89'
Nail & KC Remon. tag N. side P. Pole	S30°E 64.27'
Nail & KC Remon. tag N. side P. Pole	S40°W 65.80'
Kent Co. Mon. (I-13, T8N, R12W)	S90°W 64.81'
On C/L E-W-S Bit. Rd.	



Signed by W. R. Byl
Surveyor's Michigan License No. 23502

Date 11-17-94