

SURVEY & REMONUMENTATION

APR 28 1995

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

94 NOV 29 AM 11:48

For corners in
KENT COUNTY

(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|-----------|---|------------|------------|
| 1. Public Land Survey | T | <u>7N</u> | R | <u>12W</u> | <u>I-5</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous | S | _____ | T | _____ | _____ |
| Property in Sec. | S | _____ | T | _____ | _____ |

W. R. Byl
REG. OF DEEDS

7339

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William R. Byl, in a field survey on June 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-5	1837	GLO	Whitcomb	Set Post
	1967	Kent Co. Wit		3/4" Iron
	1972	LCRC #350	Spicer	1" Iron
	1981	LCRC #1845	Shangraw	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Carl F. Shangraw on 5/21/81 and was recorded per LCRC #1845.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-5 Found PK Nail, checks with the witnesses from LCRC #1845 for the Kent Co. Mon. as set by Carl F. Shangraw and dimensions of previous surveys. Kent Co. Mon. apparently removed during road construction after 1981.

<u>LCRC #1845</u>			
PK at C/L RR tracks	South	146.15'	
KC Nail in P. Pole	S87°E	21.45'	
KC Nail in P. Pole	S15°E	120.53'	
SE cor. of bldg.	S35°W	106.70'	

P.A. 345 1990 KENT COUNTY

PEER APPROVED 11/17/94

CHAIRMAN *W. R. Byl*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-5 Set Standard Kent County Monument in place of PK Nail.			
PK at C/L of old RR grade	South	146.20'	
KC Nail in P. Pole	S87°E	21.45'	
SE cor. of brick bldg. (newer)	S20°W	91.49'	
Cor. brick bldg. at N. cor. freight door	N45°W	52.54'	
SW cor. brick bldg.	S35°E	106.04'	
Cor. brick bldg. at N. side entry	N75°E	64.54'	



Signed by *W. R. Byl*
Surveyor's Michigan License No. 23502

Date 11-17-94