

**SURVEY & REMONUMENTATION KENT COUNTY REMONUMENTATION**

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

94 NOV 28 AM 11:48

For corners in  
KENT COUNTY COMMISSION

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T 7N R 12W I-6 \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

*Lucy Bond*  
REG. OF DEEDS

7340

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William R. Byl, in a field survey on April 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey Instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

I-6	1837	GLO	Whitcomb	Set Post
	1966	Kent Co. Wit.		2" x 2" Iron
	1978	LCRC #1126	Merdzinski	1/2" Iron
	1982	LCRC #2797	Merdzinski	Set Kent County Monument

P.A. 345 1990 KENT COUNTY,

PEER APPROVED 11/17/94  
*Handwritten Signature*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 3/25/82 and was recorded per LCRC #2797

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-6 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1/2" Iron he found. Said 1/2" Iron checks with Kent Co. Wit. and LCRC #1126

LCRC #2797

Nail & KC Remon. tag in SW side Power & Tel. Pole	S55°E	44.65'
Nail & KC Remon. tag in SW side Power & Tel. Pole	S30°E	46.06'
Nail & KC Remon. tag in N. side Power & Tel. Pole	S70°W	111.28'
NE corner of brick face of garage	S30°W	109.24'
SE corner of frame house (4.6' above grd. level)	N45°W	80.20'
Top center line of hydrant	N60°E	47.00'

West edge of manhole rim is 1.17' East of corner  
Corner is at center line intersection of Bristol Ave. and Richmond St.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-6 Standard Kent County Monument

Nail & KC Remon. tag in SW side Power & Tel. Pole	S55°E	44.65'
Nail & KC Remon. tag in SW side Power & Tel. Pole	S30°E	46.06'
Nail & KC Remon. tag in N. side Power & Tel. Pole	S70°W	111.28'
SE corner of frame house (4.6' above grd. level)	N45°W	80.20'
Top center line of hydrant	N60°E	47.35'

West edge of manhole rim is 1.17' East of corner  
Corner is at center line intersection of Bristol Ave. and Richmond St.



Signed by *W. R. Byl* Date 11-17-94  
Surveyor's Michigan License No. 23502